
State of Utah-Department of Administrative Services

AND MANAGEMENT

4110 State Office Building/Salt Lake City, Utah 84114/538-3018

DFCMPROJECT NUMBER: @311573@



000

Fire Walls

Fire Partitions Smoke Partitions

Fire Barriers

H: Actual Area: 4, 160 SQUARE FEET

G R O U P

Sheet Title: COVER SHEET


Re∨isions:

CODE REVIEW 06.30.08

PROJECT NUMBER: 01483

05.30.08 DRAWN BY: J.C.S. CHECKED BY: J.C.S. APPROVED BY: J.C.S.

SHEET NUMBER:



SUU FACILITIES MANAGEMENT ROAD IMPROVEMENT KEY

COPYRIGHT © 2008 In Site Engineering, P.C. THESE USUAL PUBLIC RECORD ACTS. REFER TO ACT 17 U.S.C. PAR. 511 (1991). WHICH PREEMPTS STATE AND LOCAL PUBLIC RECORD ACTS. REFER TO ACT 17 U.S.C. PAR. 301 (1991).

SOILS NOTE

DUE TO SOIL CONDITIONS EXISTING IN CEDAR CITY, UTAH, WHICH OCCASIONALLY CAUSE SOIL SUBSIDENCE PROBLEMS RESULTING IN DAMAGE TO STRUCTURES ENECTED THEREON, THE CITY COUNCIL OF CEDAR CITY REQUIRES PROPOSED SUBDIVISIONS TO CONDUCT TESTING OF THE SOIL CONDITIONS EXISTING IN SAID SUBDIVISION. A COPY OF THE FINDINGS OF THAT TESTING ALONG WITH RECOMMENDATIONS BASED ON THE SAME HAS BEEN FILED WITH THE SUBDIVIDER OF THE PROPERTY, WHOSE NAME AND ADDRESS ARE LISTED BELOW AND WITH THE BUILDING INSPECTOR OF CEDAR CITY. COPIES OF THIS REPORT MAY BE INSPECTED AT BOTH LOCATIONS BY THE GENERAL PUBLIC AND ANY PERSONS INTERESTED IN PURCHASING PROPERTY LOCATED WITHIN SAID SUBDIVISION.

PUBLIC WORKS DIRECTOR'S APPROVAL

I. RICK HOLMAN, PUBLIC WORKS DIRECTOR FOR CEDAR CITY CORPORATION. DO HEREBY CERTIFY THAT THESE CONSTRUCTION DRAWINGS HAVE BEEN EXAMINED AND ACCEPTED BY ME

RICK HOLMAN - PUBLIC WORKS DIRECTOR

CITY ENGINEER'S APPROVAL


I, KIT C. WAREHAM, CITY ENGINEER FOR CEDAR CITY CORPORATION, DO HEREBY CERTIFY THAT THESE CONSTRUCTION DRAWINGS HAVE BEEN EXAMINED AND ACCEPTED BY ME

KIT C. WAREHAM - CITY ENGINEER

ENGINEER'S CERTIFICATION

ALL COMMON STREETS, DRAINAGE, WATER, AND SEWER IMPROVEMENTS FOR THIS PROJECT ARE DESIGNED ACCORDING TO APPLICABLE CODES AND STANDARDS.

RONALD LARSEN P.E.



VICINITY MAP

GENERAL NOTES

1. UTILITY LOCATIONS MUST BE VERIFIED IN THE FIELD BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION, PROTECTION AND RESTORATION OF ALL BURIED OR ABOVE GROUND UTILITIES, SHOWN OR NOT SHOWN ON THE PLANS. THE CONTRACTOR MUST CALL BLUE STAKES PRIOR TO ANY EXCAVATION. (BLUE STAKES 1-800-662-4111)

2. THE GROUND SURFACE SURROUNDING THE EXTERIOR OF THE BUILDINGS SHOULD BE SLOPED TO

3. ALL IMPROVEMENTS MUST BE BUILT TO CEDAR CITY SPECIFICATIONS AND STANDARDS. ALL CONSTRUCTION SHALL BE INSTALLED AND TESTED IN ACCORDANCE WITH CEDAR CITY CORPORATION STANDARDS AND SPECIFICATIONS AND ALL APPLICABLE CODES.

4. DIMENSIONS TAKE PRECEDENCE OVER SCALING, ANY DISCREPANCIES SHOULD BE BROUGHT TO THE ATTENTION OF THE ENGINEER.

5. CONTRACTOR TO MINIMIZE ROAD CLOSURES OF EXISTING ROADS AS MUCH AS POSSIBLE. PROVIDE TRAFFIC CONTROL DEVICES AS REQUIRED FOR CONSTRUCTION AND ROAD CLOSURES PER REQUIREMENTS OF MUTCD (MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, LATEST EDITION).

6. BUILDING FOUNDATION, EXCAVATION, RETAINING WALLS, AND PAVEMENT SHOULD FOLLOW THE RECOMMENDATIONS OF THE SOILS REPORT.

7. THE CURRENT ZONE FOR THIS PROPERTY IS R3.

8. THIS PROPERTY LIES WITHIN THE AIRPORT INFLUENCE ZONE

9. THIS PROJECT DOES NOT LIE WITHIN ANY FLOOD ZONE.

10. THE BASIS OF BEARINGS FOR THIS PROJECT IS NOO'25'10"W, 1398.95 FEET FROM THE INTERSECTION OF 1275 WEST STREET AND 400 SOUTH STREET TO THE INTERSECTION P.I. OF 1275

NOTE: THIS PROJECT IS NOT ON THE CEDAR CITY GPS COORDINATE CONTROL NETWORK, THIS PROJECT IS BASED ON THE BULLOCH BROTHERS ENGINEERING CONTROL SHEET THAT WAS USED FOR CREATING ALL EXISTING SUBDIVISIONS, STREETS, AND IMPROVEMENTS IN THIS AREA.

11. BENCH MARK=B.B.E. P.K. NAIL AND FLASH AT THE INTERSECTION OF 1275 WEST STREET AND 400 SOUTH STREET. ELEVATION=5812.67. THIS IS A TEMPORARY BENCH MARK. THIS MONUMENT WILL BE REPLACED WITH A BRASS CAP CENTERLINE MONUMENT DURING CONSTRUCTION.

12. <u>ALL PUBLIC IMPROVEMENTS</u> IN 1275 WEST STREET AND 400 SOUTH STREET SHOWN ON THESE PLANS TO BE DONE BY OTHERS.

UTILITY INFORMATION

UTILITY STATEMENT: THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION, PROTECTION AND RESTORATION OF ALL BURIED OR ABOVE GROUND UTILITIES, SHOWN OR NOT SHOWN ON THE PLANS. (BLUE STAKES 1-800-662-4111)

> QUESTAR GAS JIM McPHIE

946 PRODUCTION ROAD

BRESNAN CABLEVISION

98 WEST HARDING AVENUE CEDAR CITY, UTAH 84720

(435) 865-6255

MARK MARTELL

(435) 586-8334

DARRELL OLMSTED

(435) 867-9426

CITY ENGINEERING

(435) 865-5119

KIT WAREHAM

CITY SEWER

CEDAR CITY, UTAH 84720

UTILITY CONTACTS:

ROCKY MOUNTAIN POWER KENDALL CRIPPS 2217 KITTYHAWK DRIVE CEDAR CITY, UTAH 84720 (435) 865-3380

TIM SQUIRES CEDAR CITY OFFICE (435) 586-2470

SANDY WEBB (435) 586-2967 CITY WATER

ROB MITCHELL (435) 586-2968 CITY STORM DRAIN RICK HOLMAN (435) 586-2912

SHEET INDEX

SHT.	DESCRIPTION
C1	COVER
CZ	SITE GRADING PLAN
СЗ	SITE / UTILITY PLAN
C4	PLAN AND PROFILE
C5	PLAN AND PROFILE
C6	DETAILS
<i>C</i> 7	DETAILS


ALL EXISTING UTILITY LOCATIONS MUST BE FIELD VERIFIED PRIOR TO CONSTRUCTION.



DATE: JUNE 23, 2008 SCALE: 1'=30'

JOB NO.

275@C SHEET NO:



LEGEND

- ---x---x--- EXISTING FENCE
 - FOUND MONUMENT AS DESCRIBED
 - EXISTING CENTERLINE MONUMENT
 - TBC GRADE
- (XX.XX) EXISTING GRADE
- TOP OF ASPHALT
- PROPOSED STRIPING BY CONTRACTOR
- PROPOSED DRAINAGE FLOW
- T.O.W. TOP OF WALL ELEVATION
- B.O.W. BOTTOM OF WALL ELEVATION
- PROPOSED SPILL CURB

CONSTRUCTION NOTES


- 1 NEW 24" CATCH CURB
- 2 NEW 24" SPILL CURB
- 3 PARKING LOT PAVING DESIGN 3" ASPHALT OVER 8" ROAD BASE OVER 8" TYPE 1 GRAVEL PER SOILS REPORT
- 4 NEW TRASH ENCLOSURE PER DTL.
- 5 CONCRETE APRON
- 6 CURB CUT FOR ACCESS TO NORTH PROPERTY
- 7 NEW GRAVEL DRIVE
- 8 DRAINAGE SWALE
- 9 NEW 6" CURB PER DTL.
- 10 NEW 6' SIDEWALK PER DTL. SHEET C6
- 11 4" MAX .25" SQUARE STEEL TUBING
- 12 NEW HANDICAP RAMP RAILING PER DTL.

PUBLIC IMPROVEMENTS NOTE:

ALL PUBLIC IMPROVEMENTS IN 1275 WEST STREET AND 400 SOUTH STREET SHOWN ON THESE PLANS TO BE DONE BY OTHERS.


		C	URVE	TABLE		
CURVE	LENGTH	RADIUS	TANGENT	DELTA	CHORD	CHORD BEARING
C1	18.85	12.00	12.00	90°00'00"	16.97	N44°19'24"E
C2	31.33	20.00	19.91	89°44'34"	28.22	N45°32'53"W
C3	18.85	12.00	12.00	90°00′00"	16.97	S44'34'50"W
C4	18.85	12.00	12.00	90°00'00"	16.97	S45°25'10"E
C5	7.85	5.00	5.00	90°00'00"	7.07	N44°34'50"E
C6	7.88	5.00	5.02	90°15′26"	7.09	S45°32'53"E
C7	7.85	5.00	5.00	90°00'00"	7.07	S44°19'24"W
C8	18.85	12.00	12.00	90°00′00"	16.97	S45°40'36"E


ALL EXISTING UTILITY LOCATIONS MUST BE FIELD VERIFIED PRIOR TO CONSTRUCTION.



DATE: JUNE 23, 2008 SCALE: 1'=20'


JOB NO. 275ØC





DATE: JUNE 23, 2008 SCALE: 1'=20'

JOB NO. 275@C



PROJECT LEGEND

-----SS---- NEW SEWER LINE (PVC-SDR-35) ---- W ---- NEW WATER LINE (DUCTILE IRON)

SS—— EXISTING SANITARY SEWER ---- W ---- EXISTING WATER LINE

NEW 4" SEWER LATERAL PER STD. DWG. S1 MEW 1" WATER LATERAL & METER

PER STD. DWG. W2 NEW STOP SIGN PER CC STD DWG R9

NEW STREET SIGN PER C.C. STD. DWG. R7. 00.00 TBC ELEVATION

EXISTING ASPHALT PAVING

NEW ASPHALT PAVING EXISTING SEWER MANHOLE

NEW SEWER MANHOLE

NEW FIRE HYDRANT PER C.C. STD. DWG. W2. EXISTING FIRE HYDRANT

NEW GATE VALVE

EXISTING WATER VALVE

NEW CENTERLINE MONUMENT PER C.C. STD. DWG. R7.

SECTION CORNER AS DESCRIBED

HANDICAP RAMP PER CEDAR CITY DTL. C5

DRAINAGE FLOW ARROW

NEW CONCRETE

CONSTRUCTION NOTES

1 NEW 30" CURB AND GUTTER PER DETAIL

2 NEW 6' SIDEWALK PER DETAIL

3 NEW 2"ø WATER SERVICE PER CEDAR CITY DETAIL TYP.

4 NEW 6"Ø PVC SDR-35 SEWER LATERAL PER CEDAR CITY DETAIL TYP.

5 NEW HANDICAP RAMP PER DETAIL C5

6 NEW ASPHALT PAVEMENT IN ROADWAY (SEE NOTE THIS PAGE)

7 SAW CUT AND REMOVE EDGE OF EXISTING

8 EXISTING WATER LINE TO REMAIN

9 EXISTING ASPHALT PAVING TO REMAIN

10 NEW 8"¢ CLASS 50 DUCTILE IRON WATERLINE 11 NEW FIRE HYDRANT (PER CITY DETAIL)

12 NEW 8"ø GATE VALVE

13 COMMERCIAL DRIVEWAY PER CITY DETAIL

14 EXTEND EXISITNG CROSS GUTTER PER CITY DETAIL

15 EXISTING SEWER TO REMAIN

16 STUB & CAP EXISTING 8" WATER LINE 17 EXISTING ASPHALT TO BE REMOVED

PUBLIC IMPROVEMENTS NOTE:

ALL PUBLIC IMPROVEMENTS IN 1275 WEST STREET AND 400 SOUTH STREET SHOWN ON THESE PLANS TO BE DONE BY OTHERS.

PUBLIC STREET DESIGN

1275 WEST 3.5" ASPHALT OVER 6" ROAD BASE OVER 12" COMPACTED SUBGRADE


400 SOUTH 3" ASPHALT OVER 8" ROAD BASE OVER 12" COMPACTED SUBGRADE


> ALL EXISTING UTILITY LOCATIONS MUST BE FIELD VERIFIED PRIOR TO CONSTRUCTION.





DATE: JUNE 23, 2008 SCALE: 1'=20'

JOB NO. 275@C











DATE: JUNE 23, 2008 SCALE: 1'=20'


JOB NO. 275@C



SEE SITE PLAN FOR LOCATIONS




ASPHALT SECTION



6" CURB DETAIL

TOP ()

ASPHALT



──8" BASE COURSE SPILL CURB IS IDENTIFIED BY A SHADED AREA ON


1. PROVIDE EXPANSION

JOINTS @ 25' O.C. MAX

TANGENTS, AND CORNERS


AND AT CURVES.

L-TYPE 24" F.OW CURB




L-TYPE 24" SPILL CURB

N.T.S.




4" STEEL INLET PIPE DETAIL

NOTES: ALL EXPOSED METAL PARTS SHALL BE A-36 GALVANIZED STEEL AND ALL GALVANIZING DAMAGED BY FABRICATION OR INSTALLATION SHALL RECEIVE TWO COATS OF ALUMINUM PAINT (GALVONOX OR




PARKING STALLS


1-A CURB RAMP(S) MUST BE PROVIDED ALONG AN ACCESSILBLE PATH FROM THE PARKING LOT TO CURBED SIDEWALK. 2-A RAMP IS ANY SLOPE GREATER THAN 1:20 (5%) AND SHALL HAVE A MAX. SLOPE OF 1:12 (8.33%). THE MAX. SLOPE IS 1" OF RISE PER FOOT OF DISTANCE TRAVELED. ALL DETECTABLE WARNING AREAS OF THE RAMP ARE TO HAVE A RED COLOR. 3-THE MIN. WIDTH OF ANY RAMP IS




INLINE RAMP DETAIL


N.T.S.







TYPICAL HANDICAP STALLS



CEDAR CITY TESTING REQUIREMENTS

DESCRIPTION	TEST / QUANTITY	QUANTITY	TESTS REQ'D
ROAD EMBANKMENT DENSITY TESTS	1/500 C.Y.		
ROAD SUBGRADE DENSITY TESTS	1/1,000 S.Y.	360 S.Y.	1SETS
TRENCH DENSITY TESTS		**************************************	ansår rock more men ett ger vor rede fråd ett det fråd såd en et de som en men en men et kan ett en en en en e
STORM DRAINS / CULVERTS	2/200 L.F. OF TRENCH		Aware
STORM DRAIN MANHOLES / INLET BOX	2/MANHOLE OR BOX		
IRRIGATION LINE	2/200 L.F. OF TRENCH		encon receive description of the control of the con
WATER LINE (INCLUDES F. H. & SERVICE LATERALS)	2/200 L.F. OF TRENCH	475 L.F.	3 SETS
SEWER LINE (INCLUDE SERVICE LATERALS)	5/200 L.F. OF TRENCH	53 L.F.	1 SETS
SEWER MANHOLE	5/EACH MANHOLE	A STATE OF THE STA	- SETS
VALVES	2/VALVE OR VALVE SET	2	2 SETS
UTILITY CONDUITS	2/200 L.F. OF TRENCH	e work	y mari haran caramasan arang ang kasa da kasakan da
ROAD BASE COURSE DENSITY TESTS	1/7,000 S.F.	16,906 S.F.	3 SETS
ROAD BASE THICKNESS TESTS	1/5,000 S.F.	16,906 S.F.	4 SETS
CURB/GUTTER BASE DENSITY TESTS	1/300 L.F.	772 L.F.	3 SETS
SIDEWALK BASE DENSITY TESTS	1/300 L.F.	772 L.F.	3 SETS
ASPHALT EXTRACTION TESTS	1/500 TONS OR 1 PER DAY WHICHEVER IS LESS	1 DAY	1 SET
ASPHALT DENSITY TESTS	1/7,000 S.F.	16,906 S.F.	3 SETS
ASPHALT THICKNESS TESTS	1/10,000 S.F.	16,906 S.F.	2 SETS
CONCRETE CYLINDER BREAKS	3/50 C.Y.	40 C.Y.	2 SETS
CONCRETE AIR ENTRAINMENT	2 CONSECUTIVE PASSING TESTS/LOAD	2 LOADS	2 SETS
CONCRETE SLUMP TESTS	2 CONSECUTIVE PASSING TESTS/LOAD	4 LOADS	4 SETS
ROAD BASE GRADATION TEST	1/15,000 S.F.	16,906 S.F.	2 SETS
CURB & GUTTER BASE COURSE GRAD.	1/2,000 L.F.	772 L.F.	1 SET
CURB & GUTTER THICKNESS TEST	1/200 L.F.	772 L.F.	4 SETS
SIDEWALK THICKNESS TEST	1/200 L.F.	772 L.F.	4 SETS

CONSTRUCTION NOTES: 1 RIGHT OF WAY LINE

3 CURB AND GUTTER

4 SAW CUT REQUIRED

6 CHEVRON SIGNS PER INSTALLATION DETAIL

5 ASPHALT TAPER PER SOILS


ASPHALT TAPER DETAIL


2 SIDEWALK


No. 188156 RONALD J. KARSEN

DATE: JUNE 23, 2008 SCALE: 1'=20' JOB NO.

275@C SHEET NO:








SOUTHERN UTAH UNIVERSITY

CEDAR CITY, UT

DRAWING NO: ARCH-7


DATE: 05/2003



2 DUMPSTER ENCLOSURE SECTION NOT TO SCALE

DEPARTMENT OF

FACILITIES MANAGEMENT



DUMPSTER ENCLOSURE NOT TO SCALE

State of U

G R O U

D E S I G N ARCHITECTURE

> ⊢ N

> œ

Project:
SUU
TACITIES
AANAGEMEN
OFFICE

Sheet Title: SITE DETAILS

Revisions:

Acode Review 06.30.08

PROJECT NUMBER: 01483

DATE: 05.30.08

DRAWN BY: J.C.S.

CHECKED BY: J.C.S.

APPROVED BY: J.C.S.

A1.20
SHEET NUMBER:

3 DUMPSTER ENCLOSURE SECTION NOT TO SCALE

Tangent curb cut assembly


- 1. UNTREATED BASE COURSE: Provide material specified in APWA Section 32 11 23. A. Do not use gravel as a substitute for untreated base course without ENGINEER's permission.
 - B. Place material per APWA Section 32 05 10.
 - C. Compact per APWA Section 31 23 26 to a modified proctor density of 95 percent or greater. Maximum lift thickness before compaction is 8 inches when using riding compaction equipment or 6 inches when using hand held compaction equipment.
- 2. CONCRETE: Class 4000 per APWA Section 03 30 04.
- A. If necessary, provide concrete that achieves design strength in less than 7 days. Caution, concrete crazing (spider cracks) may develop if air temperature exceeds 90 degrees F.
- B. Place concrete per APWA Section 03 30 10.
- C. Provide 1/2 inch radius on concrete edges exposed to public view. D. Cure concrete per APWA Section 03 39 00 with type ID Class A or B (clear with fugitive dye) membrane forming compound unless specified otherwise.
- EXPANSION JOINT: Make expansion joints vertical. A. Full depth 1/2 inch thick type F1 joint filler material per APWA Section 32 13 73. Set top of filler flush with surface of concrete.
- 4. CONTRACTION JOINT: Make contraction joints vertical. A. 1/8 inch wide and 1 inch deep or 1/4 slab thickness if slab is greater than 4 inches
- B. Maximum length to width ratio for non-square panels is 1.5 to 1. C. Maximum panel length (in feet) is 2.5 times the slab thickness (in inches) to a
- 5. FLARE: If a flare is in a pedestrian circulation area, the slope of the flare shall be 1:10 (10%) maximum measured perpendicular to the pedestrian access route.
- 6. DETECTABLE WARNING SURFACE: A detectable warning surface is required in a ramp, transition, or landing that provides a flush connection to the street. Perpendicular and non-perpendicular connections are shown in APWA Plan No. 238.
- PROTECTION AND REPAIR:

maximum of 15 feet.


A. Protect concrete from deicing chemicals during cure. B. Fill flow line with water. Repair construction that doesn't drain.


LANDING AT SIDEWALK LEVEL

NARRATIVE:
• SITE CONDITIONS WILL VARY, CONFIGURATION OF RAMP AND LANDING MAY BE CHANGED, BUT THEY MUST MEET DIMENSIONS AND SLOPES SHOWN HERE.
• GRADE BREAKS AT ENDS OF RAMPS MUST BE PERPENDICULAR TO THE DIRECTION OF PEDESTRIAN TRAVEL.
• USE OF FLARES, CURE WALLS, ETC., ARE AT ENGINEER'S DISCRETION.
• LENGTH OF ANY RAMP NOT REQUIRED TO EXCEED 15 FEET.



EXAMPLE 1





August 2006

		RUNNING SLOPE	CROSS SLOPE
LANDING	0	STREET GRADE	1:48 (2%)
	\odot	1:48 (2%)	STREET GRA
RAMP	(R)	1:12 (8.33%)	STREET GRA
CLEAR SPACE	(c)	1.20 (5%)	STREET CRA
	EAVEL.	RPENDICULAR TO RUNNING SLOP STRAN TRAVE	

MAXIMUM SLOPES

MATERIALS

Tangent curb cut assembly

236 Drawing 1 of 3

STANDARD DETAIL

SEE DETAIL I/AI.22 FOR DETECTABLE SURFACE

CURB AND RAMP STANDARD DETAIL

DESIGN GROU

H

R G

Re√isions:

Sheet Title:

SITE DETAILS

2CODE REVIEW 07.09.08 PROJECT NUMBER: 01483

05.30.08 DRAWN BY: J.C.S. J.C.S. CHECKED BY: APPROVED BY:

SHEET NUMBER:

A. Dome Size:

 Base diameter – 0.9 inches minimum, 1.4 inches maximum.
 Top diameter – 50 percent of the base diameter minimum to 65 percent of the base diameter maximum.

3. Height - 0.2 inches.

B. Dome Spacing: Center to center spacing – 1.6 inches minimum, 2.4 inches maximum.
 Base-to base spacing of 0.65 inches minimum measured between the most

adjacent domes. C. Dome Row Alignment:

1. Perpendicular Assembly: Perpendicular to the bottom grade break 2. Non-perpendicular Assembly Transition 1: Perpendicular to grade break at

the bottom of the ramp. 3. Non-perpendicular Assembly Transition 2: Perpendicular or radial to the flow

D. Contrast: Provide a surface that contrasts visually with adjacent walking surface

either light-on-dark, or dark-on-light. E. Size

 2 feet minimum in the direction of pedestrian travel. 2. Full width of area where a ramp, transition, or landing provides a flush

connection to the street. Minimum width of flush connection is 4 feet.

PAVER

 A. Material: ENGINEER's choice of Geotextile filter fabric, bedding and joint sand, and solid interlocking concrete paver units per APWA Section 32 14 13.

DETECTABLE SURFACE

2. Brick and mortar (not shown) per APWA Section 32 14 16. B. Layout: All out pavers are half pavers or larger.

RIBBED PANEL A. Material: CONTRACTOR's choice with ENGINEER's acceptance.

B. Layout: Trim panel, as required matching required geometries.C. Installation: Per manufacturer's recommendations.

 TILE
 A. Material: CONTRACTOR's choice with ENGINEER's acceptance. B. Layout: Trim panel, as required matching required geometries. C. Installation: Per manufacturer's recommendations.

1.6" TO 2.4" -<u>PLAN</u> OPTION: THIS AREA MAY RECEIVE DETECTABLE WARNING SURFACE 50 TO 65% OF BASE DIAMETER THIS POINT MUST -TOUCH BACK OF CURE LINE 0.9" TO 1.4" TRANSITION 1 SECTION TRUNCATED DOME DETAIL TRANSITION 2 PERPENDICULAR ASSEMBLY NON-PERPENDICULAR ASSEMBLY PAVER (NOTE 2) $2-1/2^{\circ} \times 4^{\circ} \times 8^{\circ}$ 1" DIA. DRAIN HOLES AT LOWER CORNERS. FILL HOLES WITH FEA GRAVEL. COVER HOLES WITH GEOTEXTILE. DETAIL-P DETAIL-R <u>DETAIL—T</u> Detectable warning surface 238 August **200**6

DESIGN GROUP
ARCHITECTURE | PLANNING

⊢ z

ARGE

Sheet Title: SITE DETAILS

Revisions:

CODE REVIEW 01.09.08

PROJECT NUMBER: 01483 05.30.08 DRAWN BY: J.C.S. J.C.S. CHECKED BY:

SHEET NUMBER:

APPROVED BY:



2390 WEST HIGHWAY 50 SUITE 4A CEDAR CITY, UTAH 8472 OFFICE: (435) 586-8510

artment of Administrative Services
'ACILITIES CONSTRUCTION
'MANAGEMENT
Iding/Salt Lake City, Utah 84114/538-3018

ACITIES ANAGEMENT OFFICE

Sheet Title: FLOOR PLAN

Revisions:

CODE REVIEW 04.30.08

CODE REVIEW 07.09.08

PROJECT NUMBER: 01483

DATE: 05.30.08


DRAWN BY: J.C.S.

CHECKED BY: J.C.S.

CHECKED BY: J.C.S.

APPROVED BY: J.C.S.

A210
SHEET NUMBER:
Sheet of




FLOOR PLAN SCALE: 1/4"=1'-0"




ADAAG FIGURE 27(0) DRINKING FOUNTAINS AND WATER COOLERS SPOUT HEIGHT AND KNEE CLEARANCE

DRINKING FOUNTAIN A 3 DRINKING



ENLARGED FLOOR PLAN - WOMEN'S RESTROOM SCALE:1/2"=1'-0"





DESIGN GROUP
ARCHITECTURE | PLANNING SARGENT


Sheet Title: ENLARGED FLOOR PLAN

Revisions:

CODE REVIEW 04.30.08 CODE REVIEW 07.09.08

PROJECT NUMBER: 01483 05.30.08 DRAWN BY: J.C.S. CHECKED BY: J.C.S. APPROVED BY: J.C.S.

SHEET NUMBER:



METAL STUDS AT 16" O.C

5/8" GYPSUM DRYWALL

Oź **~** ∨ ∨ ∨ บ_ั D E S I G N ARCHITECTURE

Η

æ

⊃ %

2390 WEST HIGHWAY 56 SUITE 4A CEDAR CITY, UTAH 84720 OFFICE: (435) 586-8510 FAX: (435) 586-4873

Sheet Title: REFLECTED CEILING DETAILS

Revisions:

CODE REVIEW 01.09.08

PROJECT NUMBER: 01483 DATE: 05.30.08 DRAWN BY: J.C.S. CHECKED BY: J.C.S. APPROVED BY: J.C.S.

Sheet of

A3.20 SHEET NUMBER:

BRACING DETAILS - NOT TO SCALE

METAL STUDS AT 16" O.C.

Sheet Title:

Revisions:

CODE REVIEW 06.30.08

PROJECT NUMBER: 01483


DATE: 05.30.08

DRAWN BY: J.C.S.

CHECKED BY: J.C.S.

APPROVED BY: J.C.S.

A410
SHEET NUMBER:
Sheet of




ROOF PLAN SCALE: 1/4"=1'-0"



ROOF DETAILS

NOT TO SCALE



DESIGN GROUP
ARCHITECTURE | PLANNING SARGENT

Sheet Title: ROOF DETAILS

Revisions:


CODE REVIEW 04.30.08

PROJECT NUMBER: 01483 05.30.08 DRAWN BY: J.C.S. J.C.S. CHECKED BY: APPROVED BY: J.C.S.

SHEET NUMBER: Sheet of

ELEVATION - NORTH

SCALE: 1/4"=1'-0"



ELEVATION - WEST

SCALE: 1/4"=1'-0"


ELEVATIONS


Re∨isions:

CODE REVIEW 07.09.08

PROJECT NUMBER: 01483 05.30.08 DRAWN BY: CHECKED BY: APPROVED BY:

A5.10 SHEET NUMBER:





e Services
S A R G E N T

2390 W

SUCTION
CEDAR

State of Utah-Department of Administrative S

DIVISION OF FACILITIES CONSTRU

AND MANAGEMENT

4110 State office Building/Salt Lake City, Utah 84114/538-:

Project:

Sulution

Continued to the second second

ELEVATIONS

Re√isions:

PROJECT NUMBER: 07483

DATE: 05.30.08

DRAWN BY: J.C.S.

CHECKED BY: J.C.S.

APPROVED BY: J.C.S.

A5.11
SHEET NUMBER:
Sheet of


Re∨isions:

Sheet Title:


BUILDING SECTIONS

PROJECT NUMBER: 01483 J.C.S.

SHEET NUMBER:




BUILDING CROSS SECTION
SCALE: 1/4"=1'-0"



BUILDING LONGITUDINAL SECTION
SCALE: 1/4"=1'-0"



SCALE:3/4"=1'-0"



WALL SECTION SCALE:3/4"=1'-0"

2390 WEST HIGHWAY 56 SUITE 4A CEDAR CITY, UTAH 84720 OFFICE: (435) 586-8510 FAX: (435) 586-4873 ⊢ z R G

G R O U I

D E S I G N

Sheet Title: WALL SECTIONS

Re∨isions:

PROJECT NUMBER: 01483 05.30.08 DRAWN BY: J.C.S. J.C.S. CHECKED BY: APPROVED BY: J.C.S.

SHEET NUMBER: Sheet of

PRE-ENGINEERED BLOCKING
WITH AIR SPACES FOR
VENTILATION

STRUCTURE

- VOIDS

-METAL FLASHING

-FASCIA BOARD WITH METAL CLADING

--6"X6" GUTTER WITH 4"X4" Downspout

METAL SOFFIT WITH CONTING

-DOUBLE TOP PLATE

-2X NAILER

-BOND BEAM

-FASCIA BOARD WITH METAL CLADING


PROJECT NUMBER: 01483 05.30.08 DRAWN BY: J.C.S. CHECKED BY: J.C.S.

J.C.S.

SHEET NUMBER:


APPROVED BY:

Sheet of




FIRE EXTINGUISHER CABINET DETAILS NOT TO SCALE

INSECT SCREEN TYPICAL VENT-PROFILE



NOT TO SCALE











SCALE: 1 1/2"=1'-0"



2 WALL DETAIL SCALE: 1 1/2"=1'-0" SARGENT DESIGN GROUP
ARCHITECTURE | PLANNING
2390 WEST HIGHWAY 56
SUITE 4A
CEDAR CITY, UTAH 84720



| Colect: | Co

Sheet Title: DETAILS

Re∨isions:

PROJECT NUMBER: 01483

DATE: 05.30.08

DRAWN BY: J.C.S.

CHECKED BY: J.C.S.

APPROVED BY: J.C.S.

A911
SHEET NUMBER:

).	ROOM NAME	FLOOR	BASE	WALL FINISHES				CEILING		REMARKS
				NORTH	EAST	SOUTH	WEST	MAT'L	HEIGHT	
0	ENTRY	С	С	P	P	P	P	ACT	9'-0"	
1	HALLWAY	С	С	P	P	P	P	ACT	9'-0"	
2	CINDY'S OFFICE	С	С	P	P/AWI	P	P	ACT	9'-0"	
3	DAVID'S OFFICE	С	С	P	P	P/AW2	P	ACT	9'-0"	
4	MANAGER	С	С	P/AWI	P	P	P	ACT	9'-0"	
5	MANAGER	С	С	P	P	P/AW2	P	ACT	9'-0"	
6	HALLWAY	С	С	P	P	P	P	ACT	9'-0"	
٦	MANAGER	С	С	P/AWI	P	P	P	ACT	9'-0"	
8	MANAGER	С	С	P	P	P/AW2	P	ACT	9'-0"	
9	OFFICE	С	С	P/AWI	P	P	P	ACT	9'-0"	
0	WOMEN'S RR	CT	СТ	CT/P	CT/P	CT/P	CT/P	GD	8'-0"	
1	HALLWAY	С	С	P	P	P	P	ACT	P' -0"	
2	CUSTODIAN	VCT	RUB	P	P	P	P	GD	8'-0"	CT WAINSCOTS ON 3 SIDES AT SINK
3	MEN'S RR	СТ	СТ	CT/P	CT/P	CT/P	CT/P	GD	8'-0"	
1	MECH/ELEC	VCT	RUB	P	P	P	P	GD	8'-0"	
5	CAD/CAM ROOM	С	С	P/AW2	P	P	P	ACT	9'-0"	
,	CONFERENCE RM	С	С	P	P	P/AWI	P	ACT	9'-0"	
Ī	VESTIBULE	С	С	P	P	P	P	ACT	9'-0"	
3	HALLWAY	С	С	P	P	P	P	ACT	9'-0"	
ì	OFF I CE	С	С	P/AW2	P	P	P	ACT	9'-0"	
5	BUSINESS	С	С	P	P	P/AWI	P	ACT	9'-0"	
1	WORK ROOM	С	С	P/AW2	P	P	P	ACT	9'-0"	
2	RECEPTION	С	С	P	P	P/AWI	P	ACT	9'-0"	
ENE	RAL NOTES:									ABBREVIATIONS
N	SHES: AINT - OVERALL - SHERW ACCENT - SHERW	N	_IAMS,	SW6 108	, LATT	·E				ACT - ACOUSTICAL TILE RUB - RUBBER BASE 4" CT - CERAMIC TILE VCT - VINYL COMPOSITION TILE GB - GYPSUM DRYWALL

GENERAL NOTES:


METAL FRAMES - SHERWIM WILLIAMS, ALL SURFACE ENAMEL, MESA BROWN DOOR STAIN FINISH - SHERWIN WILLIAMS, SW3119-0, BURNISHED WALNUT

BLINDS - MECO THERMO VEIL SHADE CLOTHS, 1300 SERIES DENSE BASKET WEAVE, 1302 BEIGE


CERAMIC TILE

ACOUSTICAL CEILING TILE CARPET - SUU STANDARD

BASE - SUU STANDARD, CARPET BASE







NOTE:
IF ENCLOSURES ARE USED AND
PROTRUDE OUT FROM THE WALL
THE MAX. PROJECTION SHALL
BE 19" AND CANNOT REDUCE
THE MIN. REQUIRED CLEAR WIDTH
OF THE ACCESSABLE PATH.

SIGNS TO BE CENTERED ON DOORS AND BE DISTINCTLY DIFFERENT THAN DOORS IN COLOR AND CONTRAST

INSULATE ALL EXPOSED HOT WATER AND DRAIN LINES

NOTES: I. CONTRACTOR TO PROVIDE BLOCKING/BACKING FOR ALL ACCESSORIES. BLOCKING AT GRAB BARS TO WITHSTAND A 250 LB./FT. LOAD. 2.DRINKING FOUNTAINS, TOILETS & URINALS ARE TO BE MOUNTED AS PER MANUFACTURERS RECOMMENDATIONS FOR STANDARD UNITS UNLESS THEY ARE DESIGNATED TO BE FOR HANDICAPPED USE. H.C. ACCESSABLE UNITS TO BE MOUNTED AS SHOWN ABOVE.

ADA ACCESSIBLE MOUNTING HEIGHTS

NOT TO SCALE

G R O U P

Sheet Title:

Re∨isions:

FINISH SCHEDULE

PROJECT NUMBER: 01483 05.30.08 DRAWN BY: J.C.S. J.C.S. CHECKED BY: J.C.S. APPROVED BY:

Sheet of

OI.OIA SHEET NUMBER:

Sheet Title: INTERIOR ELEVATIONS

Revisions:

PROJECT NUMBER: 01483 DATE: DRAWN BY: CHECKED BY:

APPROVED BY:


SHEET NUMBER:

05.30.08


J.C.S.

J.C.S.


J.C.S.



) INTERIOR ELEVATIONS - RESTROOMS SCALE: 1/2"=1'-0"







	HTQIW	HEIGHT	THICK.	DOOR	DOOR	DOOR	FRAME	FRAME		DETAILS		HARD-	LABEL	REMARKS
				MAT'L	TYPE	GLASS	MAT'L	TYPE	HEAD	JAMB	SILL	WARE		
00	3'-0"	7'-0"	1 3/4"	ALUM	A	TEMP	ALUM	А	4/All.30	5/AII.30	6/All.30	*	*	*
01	3'-0"	7'-0"	1 3/4"	ALUM	А	TEMP	ALUM	С	10/AII.30	11/A11.30	12/AII.30	*	*	*
02	3'-0"	7'-0"	1 3/4"	HM	В	NA	НМ	E	7/All.30	8/AII.30	9/AII.30	*	*	*
03	3'-0"	7'-0"	1 3/4"	HM	В	NA	HM	D	7/All.30				*	*
04	3'-0"	7'-0"	1 3/4"	HM	В	NA	НМ	ם	7/All.30	8/AII.30	9/AII.30	*	*	*
<i>0</i> 5	3'-0"	□ '-0"	1 3/4"	HM	В	NA	HM	ם	7/AII.30	8/AII.30	9/AII.30	*	*	*
06	3'-0"	7'-0"	1 3/4"	HM	В	NA	НМ	ם	7/AII.30	8/AII.30	9/AII.30	*	*	*
70	3'-0"	7'-0"	1 3/4"	HM	В	NA	НМ	ם	7/AII.30	8/AII.30	9/AII.30	*	*	*
08	3'-0"	ד'−0"	1 3/4"	HM	В	NA	НМ	ם	7/AII.30	8/AII.30	9/AII.30	*	*	*
09	3'-0"	□ '-0"	1 3/4"	HM	E	NA	НМ	ם	7/AII.30	8/AII.30	9/AII.30	*	*	*
10	3'-0"	7'-0"	1 3/4"	HM	E	NA	НМ	ם	7/AII.30	8/AII.30	9/AII.30	*	*	*
11	3'-0"	7'-0"	1 3/4"	HM	E	NA	НМ	ם	7/AII.30	8/AII.30	9/AII.30	*	*	*
12	3'-0"	コ′ー〇"	1 3/4"	HM	С	NA	HM	ם	7/AII.30	8/AII.30	9/AII.30	*	*	*
13	3'-0"	コ′-0″	1 3/4"	HM	В	NA	HM	D	7/AII.30	8/AII.30	9/AII.30	*	*	*
14	3'-0"	コ′ー〇"	1 3/4"	HM	В	NA	HM	ם	7/AII.30	8/AII.30	9/AII.30	*	*	*
15	3'-0"	コ′-0″	1 3/4"	HM	В	NA	HM	D	7/AII.30	8/AII.30	9/AII.30	*	*	*
16	3'-0"	コ′ー〇"	1 3/4"	HM	В	NA	HM	ם	7/AII.30	8/AII.30	9/AII.30	*	*	*
۱٦	3'-0"	7'-0"	1 3/4"	HM	В	NA	HM	D	7/AII.30	8/AII.30	9/AII.30	*	*	*
18	3'-0"	□ '-O"	1 3/4"	нм	В	NA	НМ	ם	7/AII.30	8/AII.30	9/AII.30	*	*	*
19	3'-0"	7'-0"	1 3/4"	HM	ם	NA	НМ	В	1/A11.30	2/All.30	3/AII.30	*	*	*
20	3'-0"	□ '-O"	1 3/4"	нм	В	NA	НМ	ם	7/AII.30	8/AII.30	9/AII.30	*	*	*
21	3'-0"	7'-0"	1 3/4"	НМ	В	NA	НМ	а	7/AII.30	8/AII.30	9/AII.30	*	*	*
GEN	ERAL NO	OTES:											HW - HA	<u>/iations:</u> Ardware, see spec Ollow Metal

of Utah-Department of Administrative AND MANAGEMENT

SARGENT DESIGN GROUP

| Sheet | Charlest |

Re∨isions:

SCHEDULES, DOOR AND WINDOW TYPES

PROJECT NUMBER: 01483


DATE: 05.30.08

DRAWN BY: J.C.S.

CHECKED BY: J.C.S.



APPROVED BY: J.C.S.



DESIGN GROU E Z A R G

— П П П П 14U Project: Ο Δ Δ Δ Δ Δ Δ Δ Δ Δ Δ Δ ~ ∃<<<\!\bar{\pi}


Sheet Title: DOOR DETAILS

Revisions:

04/28/08 PROJECT NUMBER: 07483

05.30.08 DRAWN BY: J.C.S. CHECKED BY: J.C.S. APPROVED BY: J.C.S.

SHEET NUMBER:



DESIGN GROUP SARGENT

Sheet Title: WINDOW DETAILS

Re∨isions: 04/28/08

PROJECT NUMBER: 07483 DRAWN BY: J.C.S. CHECKED BY: J.C.S. J.C.S. APPROVED BY:

05.30.08

SHEET NUMBER: Sheet of

GENERAL

1. THE PROJECT SPECIFICATIONS ARE NOT SUPERSEDED BY THESE GENERAL STRUCTURAL NOTES BUT ARE INTENDED TO BE COMPLIMENTARY TO THEM. CONSULT THE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS IN EACH SECTION. NOTES

AND DETAILS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES, TYPICAL DETAILS AND SPECIFICATIONS. 2. CONTRACTOR SHALL COMPARE ALL DIMENSIONS AND CONDITIONS ON DRAWINGS AND AT SITE. ALL OMISSIONS OR CONFLICTS BETWEEN THE VARIOUS ELEMENTS OF THE WORKING DRAWINGS AND/OR SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT AND OR STRUCTURAL ENGINEER BEFORE PROCEEDING WITH ANY WORK INVOLVED. IN CASE OF CONFLICT, FOLLOW THE MOST STRINGENT REQUIREMENT AS DIRECTED BY THE ARCHITECT WITHOUT ADDITIONAL COST TO THE OWNER.

3. ALL DETAILS, SECTIONS, AND NOTES SHOWN ON THE DRAWINGS ARE INTENDED TO BE TYPICAL AND SHALL APPLY TO SIMILAR SITUATIONS ELSEWHERE UNLESS NOTED OR SHOWN OTHERWISE.

4. SHORING AND BRACING REQUIREMENTS:

A. ROOF STRUCTURES - THE GENERAL CONTRACTOR IS RESPONSIBLE FOR THE METHOD AND SEQUENCE OF ALL STRUCTURAL ERECTION. HE SHALL PROVIDE TEMPORARY SHORING AND BRACING AS HIS METHOD OF ERECTION REQUIRES TO PROVIDE ADEQUATE VERTICAL AND LATERAL SUPPORT. SHORING AND BRACING SHALL REMAIN IN PLACE AS THE CHOSEN METHOD REQUIRES UNTIL ALL PERMANENT MEMBERS ARE IN PLACE AND ALL FINAL CONNECTIONS ARE COMPLETED, INCLUDING ALL ROOF AND FLOOR ATTACHMENTS. THE BUILDING SHALL NOT BE CONSIDERED STABLE UNTIL ALL CONNECTIONS ARE COMPLETE.

B. WALLS ABOVE GRADE SHALL BE BRACED UNTIL THE STRUCTURAL SYSTEM IS COMPLETE. WALLS ARE NOT SELF SUPPORTING.

5. IT SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO COORDINATE WITH ALL TRADES ANY AND ALL ITEMS THAT ARE TO BE INTEGRATED INTO THE STRUCTURAL SYSTEM. OPENINGS OR PENETRATIONS THROUGH, OR ATTACHMENTS TO THE STRUCTURAL SYSTEM THAT ARE NOT INDICATED ON THESE DRAWINGS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR AND SHALL BE COORDINATED WITH THE ARCHITECT/ENGINEER. THE ORDER OF CONSTRUCTION IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR. IT IS THE CONTRACTOR'S OBLIGATION TO PROVIDE ITEMS NECESSARY FOR HIS CHOSEN PROCEDURE.

OBSERVATION VISITS TO THE SITE BY THE STRUCTURAL ENGINEER SHALL NOT BE CONSTRUED AS INSPECTION NOR APPROVAL ON CONSTRUCTION.

7. ALL CONSTRUCTION AND INSPECTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE INTERNATIONAL BUILDING CODE. THE CONTRACTOR SHALL COORDINATE ALL REQUIRED INSPECTIONS AND SHALL NOT PROCEED WITH THE WORK INVOLVED UNTIL THE INSPECTIONS HAVE BEEN DONE.

8. ALL WORKMANSHIP AND MATERIALS SHALL CONFORM TO THE REQUIREMENTS OF THE LATEST EDITION OF THE INTERNATIONAL BUILDING CODE.

THE CONTRACTOR MUST SUBMIT A WRITTEN REQUEST FOR, AND OBTAIN THE ARCHITECT'S AND /OR THE STRUCTURAL ENGINEER'S WRITTEN PRIOR APPROVAL FOR ALL CHANGES, MODIFICATIONS. AND/OR SUBSTITUTIONS.

THE CONTRACTOR SHALL COORDINATE AND VERIFY ALL DIMENSIONS AND ELEVATIONS SHOWN ON STRUCTURAL DRAWINGS WITH THE ARCHITECTURAL DRAWINGS.

11. SEE THE ARCHITECTURAL DRAWINGS FOR DIMENSIONS, DOORS, WINDOWS, NONBEARING INTERIOR AND EXTERIOR WALLS. ELEVATIONS, SLOPES, STAIRS, CURBS, DRAINS, RECESSES, DEPRESSIONS, RAILING, WATERPROOFING, FINISHES, CHAMFERS. KERFS. ETC.

12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SAFETY AND PROTECTION ON/AROUND THE JOB SITE AND/OR ADJACENT PROPERTIES.

13. CONTRACTOR MUST FIELD VERIFY ALL EXISTING CONDITIONS TO MATCH DETAILS SHOWN ON DRAWINGS. IF ANY CONFLICTING CONDITIONS ARISE DURING CONSTRUCTION, CONTRACTOR MUST NOTIFY STRUCTURAL ENGINEER BEFORE PROCEEDING WITH FABRICATION OR CONSTRUCTION.

14. THERMAL OR MOISTURE PROTECTION, FURNISHINGS, DOORS, WINDOWS, EQUIPMENT, MECHANICAL, ELECTRICAL, FINISHES, SIDING, PANELING, VENEERS ARE NOT PART OF THE RESPONSIBILITY OF THE STRUCTURAL ENGINEER.

15. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO LOCATE ALL EXISTING UTILITIES WHETHER SHOWN HERON OR NOT, AND TO PROTECT THEM FROM DAMAGE. THE CONTRACTOR SHALL BEAR ALL EXPENSE OF REPAIR OR REPLACEMENT IN CONJUNCTION WITH THE REQUIRED WORK.

MINIMUM COMPRESSIVE STRENGTH OF CONCRETE IN 28 DAYS AS FOLLOWS:

ALL CONCRETE 4000 PSI, TYPE"V" CEMENT, AND W/C LESS THAN OR EQUAL TO 0.5 CONCRETE DENSITY:

NORMAL WEIGHT CONCRETE SHALL BE APPROXIMATELY 145 PCF.

3. MILD STEEL REINFORCING: DEFORMED BARS, ASTM A-615, GRADE 60 WITH MINIMUM YIELD STRENGTH 60 KSI. 4. REINFORCEMENT PROTECTION:

CONCRETE PLACED AGAINST THE EARTH...3"

CONCRETE PLACED IN FORMS BUT EXPOSED TO EARTH OR WEATHER...........1-1/2"

COLUMNS, BEAMS.....1-1/2"

SLABS OR WALLS NOT EXPOSED TO EARTH OR WEATHER...........3/4" ADMIXTURES:

AIR-ENTRAINING ADMIXTURES (WHEN USED), COMPLY WITH ASTM C260. CALCIUM CHLORIDE SHALL NOT BE ADDED TO CONCRETE MIX.

6. CONSTRUCTION JOINTS AND CONTROL JOINTS:

A. PROVIDE A CONTINUOUS TOOL ROUGHENED SURFACE TOP OF ALL WALL FOOTINGS, UNLESS NOTED OTHERWISE. ALL HORIZONTAL AND VERTICAL CONSTRUCTION JOINTS SHALL HAVE A CONTINUOUS 2" X 4" KEYWAY ALONG THE

JOINT, UNLESS NOTED OTHERWISE, SEE DETAILS. PROVIDE REINFORCING DOWELS TO MATCH THE MEMBER REINFORCING AT THE JOINT, UNLESS NOTED OTHERWISE.

SLABS AND BEAMS SHALL NOT HAVE JOINTS IN HORIZONTAL PLANE SLABS-ON-GRADE SHALL HAVE CONSTRUCTION OR CONTROL JOINTS PLACED IN LENGTHS NOT TO EXCEED 36 TIMES

THE SLAB THICKNESS IN ANY DIRECTION. CONSTRUCTION JOINTS SHALL NOT EXCEED A DISTANCE OF 125' O" O.C. IN ANY DIRECTION. F. ALL CONSTRUCTION AND CONTROL JOINTS AS DETAILED OR AS APPROVED BY STRUCTURAL ENGINEER.

CONTROL JOINTS SHALL BE COMPLETE WITHIN 12 HOURS OF CONCRETE PLACEMENT. 7. MINIMUM REINFORCING:

A. WALL REINFORCING SHALL BE AS FOLLOWS, UNLESS NOTED OTHERWISE:

WALL THICKNESS HORIZONTAL REINF. VERTICAL REINF.

#4 @ 12" O.C. #4 @ 32" O.C. PLUS #5 MASONRY DOWEL @ 32" O.C.

B. PLACE STEEL IN THE CENTER OF THE WALL (EXCEPT IN WALLS THICKER THAN 10" AND WHERE SHOWN OTHERWISE). IN ADDITION TO THE ABOVE REINFORCING, 2-#5 X CONTINUOUS HORIZONTAL BARS SHALL BE PLACED AT THE BOTTOM OF THE WALL (NEAR THE FOOTING) AND AT THE TOP OF THE WALL.

8. NO SPLICES OF REINFORCEMENT PERMITTED EXCEPT AS DETAILED OR AUTHORIZED BY STRUCTURAL ENGINEER. MAKE BARS CONTINUOUS AROUND CORNERS. WHERE PERMITTED, SPLICES MADE BY CONTACT LAPS. 57 BAR DIAMETERS MINIMUM. 9. PROVIDE ACCESSORIES RECOMMENDED BY THE CRSI NECESSARY TO PROPERLY SUPPORT REINFORCING AT POSITIONS

SHOWN ON PLANS. 10. DETAIL BARS IN ACCORDANCE WITH ACI 315 "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCING CONCRETE STRUCTURES". CONCRETE REINFORCING STEEL INSTITUTE (CRSI) RECOMMENDATIONS, AND "BUILDING CODE

REQUIREMENTS FOR REINFORCED CONCRETE", ACI 318. 11. PLACE 2- #5 WITH 2'-0" PROJECTION AROUND OPENINGS IN CONCRETE.

12. CONTINUOUS TOP AND BOTTOM BARS IN WALLS SPLICED AS FOLLOWS:

TOP BARS - AT MIDSPAN BOTTOM BARS - OVER SUPPORT

13. ALL VERTICAL REINFORCING SHALL BE DOWELED TO FOOTINGS, OR THE STRUCTURE BELOW. DOWELS SHALL BE THE SAME SIZE AND AT THE SAME SPACING AS THE VERTICAL WALL REINFORCING SCHEDULED FOR THE WALL ABOVE. LAP LENGTHS SHALL COMPLY AS NOTED ABOVE OR AS SHOWN IN THE DRAWINGS. DOWELS EXTENDING INTO FOOTINGS SHALL TERMINATE WITH A 90 DEGREE STANDARD ACI HOOK AND SHALL EXTEND TO WITHIN 4" OF THE BOTTOM OF THE FOOTING.

14. HORIZONTAL WALL REINFORCING SHALL TERMINATE AT ENDS OF WALLS, CORNERS AND OPENINGS INTO THE FAR END OF THE JAMB COLUMN WITH A 90 DEGREE HOOK + 6 BAR DIAMETER EXTENSION, UNLESS SHOWN OTHERWISE. LAP HORIZONTAL BAR SPLICES AS NOTED ABOVE OR AS SHOWN ON THE DRAWINGS. HORIZONTAL WALL REINFORCING SHALL BE CONTINUOS THROUGH CONSTRUCTION AND CONTROL JOINTS. SPLICES IN HORIZONTAL REINFORCEMENT SHALL BE STAGGERED. SPLICES IN TWO CURTAINS WHERE USED SHALL NOT OCCUR IN THE SAME LOCATION.

15. NO WELDING OF REINFORCEMENT SHALL BE PERMITTED UNLESS APPROVED BY STRUCTURAL ENGINEER.

16. ALL FORMWORK SHALL COMPLY WITH REQUIREMENTS OF ACI STANDARD PUBLICATION NO 347. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, CARE, DETAILING, PLACEMENT AND REMOVAL OF ALL FORMWORK AND SHORING. 17. CONTRACTOR SHALL COORDINATE PLACEMENT OF ALL OPENINGS, CURBS, DOWELS SLEEVES, CONDUITS, BOLTS AND INSERTS PRIOR TO CONCRETE PLACEMENT. NO ALUMINUM CONDUIT OR PRODUCT CONTAINING ALUMINUM OR ANY OTHER

MATERIAL INJURIOUS TO CONCRETE SHALL BE EMBEDDED IN CONCRETE.

18. THE SAMPLES FOR TESTS OF EACH STRENGTH OF CONCRETE SHALL BE TAKEN NOT LESS THAN ONCE A DAY, NOR LESS THAN ONCE FOR EACH 150 CUBIC YARD OF CONCRETE, NOR LESS THAN ONCE FOR EACH 5000 SQUARE FT. OF SURFACE AREA FOR SLABS OR WALLS, NOR LESS THAN FIVE TIMES THROUGHOUT THE PROJECT.

1. MINIMUM COMPRESSIVE STRENGTH OF CONCRETE MASONRY UNIT BASED ON MINIMUM NET AREA SHALL BE 1900 (LIGHTWEIGHT GRADE N). MASONRY TO DEVELOP MINIMUM ULTIMATE COMPRESSIVE STRENGTH (F'M) OF 1500 PSI. MORTAR SHALL BE TYPE (S) ACCORDING TO IBC SECTION 2103.8 AND SHALL COMPLY WITH ASTM C 270. AGGREGATES

USED IN MORTAR SHALL COMPLY WITH ASTM C 144. ADDITIVES OR ADMIXTURES SHALL NOT BE USED IN MORTAR MIX. GROUT FOR CONCRETE MASONRY UNIT SHALL BE PROPORTIONED ACCORDING TO IBC SECTION 2103.10.7 AND SHALL DEVELOP COMPRESSIVE STRENGTH OF 2000 PSI WITHIN 28 DAYS. AGGREGATES USED IN GROUT SHALL BE SAND AND GRAVEL AND SHALL COMPLY WITH ASTM C 404. ADDITIVES OR ADMIXTURES SHALL NOT BE USED IN GROUT MIX.

REINFORCEMENT USED IN MASONRY CONSTRUCTION SHALL BE DEFORMED BARS, ASTM A-615 GRADE 60 (FY=60 K.S.I.). ALL REINFORCEMENT, ANCHOR BOLTS AND HEADED STUDS SHALL BE SET IN SOLID GROUTED CELLS. GROUTING SHALL COMPLY WITH IBC SECTION 2104. GOUT SHALL BE MECHANICALLY CONSOLIDATED ACCORDING TO ACI 530.1/ASCE6/TMS602.3.5.

SPLICES ARE NOT PERMITTED IN REINFORCING BARS EXCEPT AS DETAILED OR AUTHORIZED BY STRUCTURAL ENGINEER. WHERE PERMITTED, SPLICES MADE BY CONTACT LAPS, A MINIMUM OF 48 BAR DIAMETERS. MINIMUM REINFORCING:

A. ALL MASONRY WALLS SHALL BE REINFORCED AS FOLLOWS, UNLESS SHOWN OTHERWISE ON THE DRAWINGS:

CMU WALLS: #5 VERTICAL AT 32" O.C. (1) -#4 HORIZONTAL AT 24" O.C. SOLID GROUTED

B. IN ADDITION TO THE ABOVE REINFORCING, LADDER-TYPE WIRE JOINT REINFORCING (DUR-O-WALL) CONSISTING OF 2-#9 WIRES SHALL BE USED HORIZONTALLY AT 16" O.C. IN ALL MASONRY WALLS. JOINT REINFORCING SHALL BE THE STANDARD WIDTH FOR THE WALL THICKNESS IT IS REINFORCING. 8. REINFORCEMENT PROTECTION (COVER):

JOINT REINFORCEMENT SHALL HAVE NOT LESS THAN 5/8" MORTAR COVERAGE FROM THE EXPOSED FACE. B. OTHER REINFORCEMENT SHALL HAVE A MINIMUM COVERAGE OF ONE BAR DIAMETER OVER ALL THE BARS, BUT NOT

LESS THAN 1-1/2". WHEN MASONRY IS EXPOSED TO WEATHER OR SOIL, MINIMUM COVERAGE SHALL BE 2". CONTINUE VERTICAL REINFORCEMENT BARS IN MASONRY COLUMNS THRU FOUNDATION WALL INTO FOOTINGS WITH MATCHING BARS AND DOWELS. ENCLOSE THESE BARS WITH SAME SIZE TIES AT SAME SPACING AS IN MASONRY COLUMN. PROVIDE MATCHING DOWELS FOR VERTICAL BARS IN MASONRY WALLS TO STRUCTURE BELOW.

10. CONTINUE HORIZONTAL REINFORCEMENT IN WALLS THRU MASONRY COLUMNS AND PILASTERS. THIS REINFORCEMENT SHALL HAVE MATCHING DOWELS, CORNER BARS, AT CORNERS AND AT INTERSECTIONS OF THE WALLS WITH REQUIRED LAP

11. UNLESS NOTED OTHERWISE, HOLLOW CELLS AT ALL (4) SIDES OF OPENINGS IN WALLS SHALL BE GROUTED AND REINFORCED WITH 2- #5, MINIMUM 2'-8" PROJECTION AT EACH END.

12. FILL VOIDS AND BLOCK CELLS SOLIDLY WITH GROUT A DISTANCE OF 24" EACH SIDE OF BEAM REACTIONS OR CONCENTRATED LOADS U.N.O.

13. ALL MASONRY WALLS SHALL HAVE VERTICAL CONTROL JOINTS AT MAJOR CHANGES IN WALL HEIGHT, AT CHANGES IN WALL 6. THICKNESS, AT BUILDING CONSTRUCTION JOINTS, AND NOT FURTHER APART THAN 25 FEET ELSEWHERE. PROVIDE MATCHING CONTROL JOINTS FOR BRICK VENEER, REFER TO DETAILING ON DRAWINGS & CONSULT ARCHITECTURAL DRAWINGS FOR LOCATIONS.

\times	LEVEL 2 INSPECTION REQUIRED (MASONRY UNITS. WALL PRISMS)
	SUBSEQUENT TESTS (MORTAR, GROUT, FIELD WALL PRISMS)
X	PLACEMENT INSPECTION OF UNITS
X	ANCHOR BOLT PLACEMENT IN MASONRY

X	EPOXY ANCHOR PLACEMENT	

STRUCTURAL SPECIAL INSPECTION SCHEDULE REINFORCED CONCRETE, GROUT & MORTAR.

CONCRETE	GROUT	MORTAR	
			AGGREGATE TESTS
			REINFORCING TESTS
\times	\times	X	MIX DESIGNS
\times			REINFORCING PLACEMENT
	Transfer		BATCH PLANT INSPECTION
			INSPECT PLACING
\times	\times	X	CAST SAMPLES
			PICK UP SAMPLES
X	X	X	COMPRESSION TESTS
X			ANCHOR BOLT PLACEMENT

DESIGN CRITERIA

1. GOVERNING BUILDING CODE: 2006 INTERNATIONAL BUILDING CODE (IBC)

2. GRAVITY LIVE LOADS USED IN DESIGN:

A. ROOF......30 PSF $B. I_S = 1.0$

3. SEISMIC LOADING; A. SEISMIC USE GROUP I

B. SEISMIC DESIGN CATEGORY D $C. S_{DS} = 0.579 S_{D1} = 0.290$ D. SITE CLASS = D $I_F = 1.0$

E. R = 5.0

4. WIND LOADING: A. VELOCITY V3S = 90 MPH VFM = 75 MPH B. EXPOSURE CATEGORYC

 $C. l_W = 1.0$

5. FOUNDATIONS

A. SOIL BEARING PRESSURE....2000 PSF

B. FOUNDATION DESIGN WAS OBTAINED FROM A SOILS REPORT PREPARED BY GEM ENGINEERING. REPORT NUMBER RG0828 DATED JUNE 13, 2008. ALL EXCAVATION, FILL, COMPACTION, AND PLACEMENT PERFORMED, SHALL COMPLY WITH RECOMMENDATIONS OUTLINED IN THE ABOVE REFERENCED REPORT.

HESE PLANS ARE INSTRUMENTS OF PROFESSIONAL SERVICE AND ARE PROTECTED BY COMMON LAW, STATUTORY AND OTHER RESERVED RIGHTS INCLUDING COPYRIGHT. THEY MAY NOT BE REPRODUCED OR USED FOR ANY PURPOSE WITHOUT THE WRITTEN CONSENT OF SARGENT DESIGN GROUP

1. ALL PLYWOOD ROOF & FLOOR DIAPHRAGMS AND SHEAR WALLS SHALL BE APA RATED STRUCTURAL SHEATHING WITH A SPAN INDEX RATING AND THICKNESS AS NOTED ON DRAWINGS. EDGE SUPPORT, IF REQUIRED BY SPAN RATING OR THE PLYWOOD AND JOIST SPACING, SHALL CONSIST OF LUMBER BLOCKING. PANEL EDGE CLIPS, OR TONGUE AND GROOVE PLYWOOD EDGES.

2. ALL MEMBERS FRAMING INTO THE SIDE OF HEADERS OR STUD WALLS SHALL BE ATTACHED USING METAL

JOIST HANGERS 3. ALL BOLTS FOR CONNECTIONS SHALL HAVE WASHERS PLACED UNDER NUTS AND HEADS. BOLT HOLES TO BE DRILLED 1/16" LARGER THAN BOLT DIAMETER.

MATERIALS: A. GLU LAM TIMBER: DOUGLAS FIR COMBINATION SYMBOL 24F-V4 FOR BEAMS (SIMPLE SPANS); 24F-V8 FOR CONTINUOUS OR CANTILEVER CONDITIONS. FB=2400 PSI, E=1,800,000 PSI. B. FRAMING LUMBER: NUMBER 2 DOUGLAS FIR-LARCH OR BETTER OR AS NOTED OTHERWISE; MIN

FB=1035 PSI FOR REPETITIVE USE. C. PLYWOOD INTERIOR GRADE WITH EXTERIOR GLUE, SPAN INDEX RATIO: 24/16 (3/4")

5. NAILS: STANDARD COMMON. MINIMUM NAILING REQUIREMENTS (SEE DRAWINGS FOR AREAS WITH GREATER REQUIREMENTS):

A. ROOF: NAIL ALL PLYWOOD PANEL EDGES WITH 10d COMMON NAILS AT 6" O.C. AT ALL PANEL EDGES AND AT 12" O.C. AT ALL INTERMEDIATE SUPPORTS. UNLESS BLOCKING IS SPECIFICALLY REQUIRED ON THE DRAWINGS, USE TWO PLYCLIPS BETWEEN EACH SUPPORT FOR SPANS OF 48" O.C. AND ONE PLYCLIP BETWEEN EACH SUPPORT FOR LESSER SPANS AT ALL UNSUPPORTED PLYWOOD PANEL EDGES. B. GENERAL FRAMING AND CARPENTRY: CONNECT ALL ITEMS AS PER I.B.C. CHAPTER 23, AND TABLE

2304.9.1 UNLESS NOTED OTHERWISE. C. FRAMING CONNECTIONS: USE SIMPSON STRONG-TIE CONNECTORS OR APPROVED EQUIVALENT.

1. JOIST AND RAFTERS: "U" OR "F" HANGERS AS REQUIRED. 2. BEAMS: EG HANGERS AND HGLB BEAMS SEATS

3. HINGE CONNECTORS: HC 3T

4. COLUMNS: CC CAPS AND CB COLUMN BASES

5. HOLD DOWN ANCHORS: HD AND FTA 6. BLOCKING, BRIDGING, AND BRACING

PROVIDE SOLID BLOCKING AT LEAST 2 IN. NOMINAL THICK AND FULL DEPTH OF JOIST AT ENDS AND AT EACH SUPPORT OF JOIST. PROVIDE APPROVED BRIDGING AT A MAXIMUM OF 8'-0" O.C. BETWEEN ROOF JOIST SUPPORTS. SOLID BLOCKING BETWEEN JOISTS SHALL BE ATTACHED TO THE WOOD PLATE

AT THE TOP OF THE WALL PER STRUCTURAL DETAILS. LAMINATED BUILT-UP BEAMS OF 2X MEMBER 10 IN. OR LESS IN DEPTH SHALL BE SPIKED TOGETHER WITH NOT LESS THAN 16d COMMON NAILS AT TWELVE-INCH (12 IN.) CENTERS, STAGGERED UNLESS SO SPIKED, OR IF THE DEPTH OF BEAM IS MORE THAN TEN INCHES (10 IN.), THE LAMINATIONS SHALL BE CONNECTED TOGETHER WITH 1/2 IN. BOLTS AT 18 IN. O.C. STAGGERED. BOLTS SHALL BE PLACED 1/4 THE DEPTH OF THE MEMBER FROM THE TOP AND BOTTOM OF THE MEMBER.

7. FASTENERS FOR PRESERVATIVE-TREATED AND FIRE-RETARDANT-TREATED WOOD SHALL MEET THE REQUIREMENTS OF IBC 2304.9.5 AND SHALL BE OF HOT DIPPED ZINC-COATED GALVANIZED STEEL, STAINLESS STEEL, SILICON BRONZ OR COPPER. THE COATING WEIGHTS FOR ZINC-COATED FASTENERS SHALL BE IN ACCORDANCE WITH ASTM A153.

8. PRE-FAB WOOD TRUSSES SHALL BE DESIGNED BY A UTAH REGISTERED ENGINEER. ALL DIMENSIONS SHALL BE VERIFIED IN THE FIELD PRIOR TO FABRICATIONS OF TRUSSES. PROVIDE CROSS BRACING, CONNECTIONS, AND INSTALLATION AS REQUIRED BY TRUSS MANUFACTURER. TRUSS MANUFACTURER SHALL PROVIDE DESIGN, CONNECTIONS, LOCATIONS & AMOUNTS OF CONTINUOUS STRINGERS AND NAILING SCHEDULES OF GIRDERS & COMPONENTS

SPECIAL INSPECTION & NONDESTRUCTIVE TESTING REQUIREMENTS

1. SPECIAL INSPECTION AND NONDESTRUCTIVE TESTING SHALL BE PERFORMED BY AN INDEPENDENT TESTING AGENCY AND SHALL BE PAID FOR BY THE OWNER.

2. WHERE RESULTS OF INSPECTIONS OR TESTS DO NOT INDICATE COMPLIANCE WITH CONTRACT DOCUMENTS. RE-TESTS MAY BE REQUIRED PER ENGINEER'S DISCRETION 3. FOUNDATIONS/SOILS

REQUIRED DURING EARTHWORK EXCAVATIONS AND COMPACTION OPERATIONS FOR COMPLIANCE WITH REQUIREMENTS GIVEN IN SOILS REPORT. CONCRETE

A. REQUIRED DURING THE TAKING OF SPECIMENS AND PLACEMENT OF REINFORCING STEEL AND CONCRETE, AS PER IBC. SECTION 1704.4

BOLTS PLACED IN CONCRETE REQUIRE INSPECTION PER IBC, SECTION 1704.4 EPOXY ANCHORS: CONTINUOUS INSPECTION SHALL BE PERFORMED DURING INSTALLATION. STRUCTURAL MASONRY AS REQUIRED PER IBC, TABLE 1704.5.3 FOR ALL NEW MASONRY CONSTRUCTION 7. A COPY OF ALL SPECIAL INSPECTION/TESTING REPORTS SHALL BE PROVIDED TO THE BUILDING

DEPARTMENT, ARCHITECT AND STRUCTURAL ENGINEER. 8. ALL THE APPROPRIATE RECORDS, CERTIFICATIONS, AND PERTINENT CREDENTIALS FOR EACH INSPECTOR. MUST BE SUBMITTED TO THE ARCHITECT/ENGINEER FOR APPROVAL PRIOR TO COMMENCING WITH THE

9. PRE-FAB WOOD TRUSSES SHALL BE DESIGNED BY A UTAH REGISTERED ENGINEER. ALL DIMENSIONS SHALL BE VERIFIED IN THE FIELD PRIOR TO FABRICATIONS OF TRUSSES. PROVIDE CROSS BRACING CONNECTIONS, AND INSTALLATION AS REQUIRED BY TRUSS MANUFACTURER. TRUSS MANUFACTURER SHALL PROVIDE DESIGN, CONNECTIONS, LOCATIONS & AMOUNTS OF CONTINUOUS STRINGERS AND NAILING SCHEDULES OF GIRDERS & COMPONENTS

SHOP DRAWINGS SUBMITTALS


1. CONTRACTOR SHALL REVIEW AND VERIFY ALL SHOP DRAWINGS TO ASSURE THEY COMPLY WITH REQUIREMENTS OF THE CONTRACT DOCUMENTS. ENGINEER WILL REVIEW THE SHOP DRAWINGS FOR GENERAL CONFORMANCE WITH DESIGN CONCEPT. THIS REVIEW BY THE ENGINEER SHALL NOT BE CONSTRUED AS APPROVAL

2. PROVIDE 4 SETS OF SHOP DRAWINGS TO ENGINEER FOR REVIEW FOR THE FOLLOWING BUT NOT LIMITED TO FOUNDATION & MASONRY WALL REINFORCEMENT, CONCRETE MIX DESIGN, STRUCTURAL MASONRY ELEMENTS, STRUCTURAL STEEL, AND STEEL JOIST & DECK. REFER TO ARCHITECTURAL DRAWINGS FOR SHOP DRAWING SUBMITTAL REQUIRED FOR NON-STRUCTURAL ELEMENTS. DRILL & EPOXY ANCHORS

1. USE HIT-RE 500-SD ADHESIVE SYSTEM OR EQUIVALENT FOR CONCRETE AND SOLID GROUTED MASONRY CONNECTIONS.

2. 10% OF ALL ANCHORS PLACED SHALL BE RANDOMLY TESTED TO 110% OF MANUFACTURER SPECIFIED ALLOWABLE LOAD. IF ANY ANCHOR FAILS IT SHALL BE REPLACED AND RETESTED AT NO ADDITIONAL COST TO THE OWNER. IF AN ANCHOR FAILS, 100 % OF ALL ANCHORS INSTALLED BY THE SAME CREW SHALL BE TESTED AT NO ADDITIONAL COST TO THE OWNER.

REFER TO 2006 I.B.C. CHAPTER 17 FOR ADDITIONAL INFORMATION AND ARCHITECTURAL DRAWINGS & GEOTECHNICAL REPORT FOR ADDITIONAL INSPECTION REQUIREMENTS FOR NON-STRUCTURAL ITEMS.



Sultah tah 867

Project:

SUU FACILITIES

MGMT. BUILDING

Z

Sheet litle: GENERAL STRUCTURAL NOTES

<u>ت</u> د

O

CZ Z

ල 🖫

_ :


SE

_ □ ₹

Revisions:

PROJECT NUMBER: DATE: DRAWN BY: CHECKED BY: APPROVED BY:

SHEET NUMBER:



S A R G E N T D E S I G N G R O U P ARCHITECTURE | PLANNING 2390 WEST HIGHWAY 56

2390 WEST HIGHWA' SUITE 4A CEDAR CITY, UTAH 8 OFFICE: (435) 586-85 FAX: (435) 586-487

FACILITIES CONSTRUC

SUU FACILIES MANAGEMENT OFFICE

Sheet Title: FOUNDATION PLAN

Re∨isions:

CODE REVIEW 04.21.08

CODE REVIEW 01.09.08

PROJECT NUMBER: 01501


DATE: 05.30.08

DRAWN BY: J.C.S.

CHECKED BY: J.C.S.

APPROVED BY: J.C.S.

S2.0
SHEET NUMBER:




G R O U P

Sheet Title: ROOF FRAMING

Revisions: ACODE REVIEW 07.09.08

PROJECT NUMBER: 07507 05.30.08 DRAWN BY: J.C.S. CHECKED BY: J.C.S.

SHEET NUMBER:



Sheet Title: MECHANICAL FLOOR PLANS & SECTION


|Revisions:

<u>/1</u> 15 JULY 2008

PROJECT NUMBER: DATE: 5 MAY 2008 DRAWN BY: BRR CHECKED BY: RJR APPROVED BY: RJR

M-1

SHEET NUMBER:



3. REMOTE CEILING DAMPER REGULATORS ARE REQUIRED ON ALL BALANCE DAMPERS THAT ARE NOT LOCATED DIRECTLY ABOVE REMOVABLE CEILINGS.

4. PRIOR TO FINAL INSPECTION PROVIDE "GREEN STICKER" TO VERIFY THAT ALL GAS APPLIANCES HAVE BEEN ADJUSTED FOR ALTITUDE AND GAS CONTENT.

5. WRAP ALL OUTSIDE AIR DUCTS WITH EXTERNAL INSULATION.

6. ALL PVC EQUIPMENT VENTS, PLUMBING VENTS, AND PENTHOUSES SHALL BE PAINTED TO MATCH ROOF COLOR.

7. ALL DUCT WORK AND VENTS ARE TO BE SUPPORTED AS PER SMACNA STANDARD BRACING REQUIREMENTS INCLUDING SEISMIC BRACING WHERE REQUIRED.

8. ALL SUPPLY AND RETURN DUCT IS TO BE LINED WITH 1" ACOUSTICAL LINER UNLESS OTHERWISE NOTED.

16X18 RA-

∕8X8 OSA-

12X10 RA

16X18 RA

16X18 SA

114 MECHANICAL/

VENT PIPING

(TYPICAL)

CC

20" HIGH

SCALE: 1/4"=1'-0"

RA PLENUM (TYPICAL)

ELECTRICAL

8X8 05A

16X18 RA 16X16 RA

MECHANICAL SECTION

∕12X10 RA

√16X18 RA

∠MOTORIZED DAMPER

(TYPICAL)

(TYPICAL)

(TYPICAL)

FLEXIBLE CONNECTOR (TYPICAL)


FILTER RACK

M-1


-ACCESS DOOR

MANUAL DAMPER

9. ALL SUPPLY AND RETURN DUCTS ABOVE THE CEILING SPACE ARE TO BE WRAPPED WITH 2" INSULATION FOR A COMBINED INSULATION VALUE OF R-8 OR BETTER.




DESIGN CONDITIONS	OUTSIDE	INSIDE
WINTER	2°F	70°F
SUMMER	93°F db, 59°F wb	72°F db, 64°F wb




















MECHANICAL FLOOR PLAN

SCALE: 1/4"=1'-0"

CU 2

ENTRY

∕-6''¢

102

CINDY'S OFFICE

R-1

120


BUSINESS


8''Ф

103

DAVID'S OFFICE


√10X8





	REGIS	TER,	LOUVER	& GRII	LE SC	CHEDULE
MARK	TYPE		SERVICE	CFM RANGE	NOMINAL SIZE	REMARKS
R-1	CEILING	3	RA	110-200	8X8	2
R-2	CEILING	3	RA	250-260	10X10	2
R-3	CEILING	3	RA	360-370	12X12	2
R-4	CEILING	3	RA	800	20X20	2
PH-1	PENTHOUSE		EA	200	8X8	456
PH-2	PENTHOUSE		OSA	550	12X12	456

- 1) MAXIMUM NC=25 @ MAXIMUM CFM NOTED.
- 2 SEE SPECIFICATIONS FOR APPROVED MANUFACTURERS.
- 3 FINISH SHALL BE OFF-WHITE BAKED ENAMEL.
- (4) BAKED ENAMEL FINISH TO MATCH ROOF COLOR OR COLOR AS DIRECTED BY ARCHITECT.
- (5) PROVIDE ALUMINUM BIRD SCREENS.
- (6) MAX. ACCEPTABLE FACE VELOCITY THROUGH NET FREE AREA: 400 FT/MIN.



	DIFFUSER SCHEDULE 23										
MARK	C.F.M. RANGE	DIFFUSER SIZE	NECK. CONN.	BLOW	PATTERN	AIR DIST./SIDE A (%) B(%)					
D- 1	50	6X6	6''Ф	4 WAY	A A A B	25	25				
D- 2	110-200	9X9	8''Ф	4 WAY	Ø Å Å B	25	25				
D- 3	200-280	12X12	10''ф	4 WAY	A A B A	25	25				
D- 4	150	12X12	10''Ф	2 WAY	A⊴□⊳B	50	50				
D- 5	200	12X12	10''Ф	3 WAY	△ A △ B	33	33				

- MAXIMUM NC=25 @ MAXIMUM CFM NOTED.
- 2 SHALL BE TITUS TDC TYPE 6 OR EQUAL BY OTHER APPROVED MANUFACTURERS. (SEE SPECIFICATIONS)
- 3 FINISH SHALL BE OFF-WHITE BAKED ENAMEL.

	EXHAU	ST F	AN SCHE	EDULE	23
MARK	SERVES ROOM	MIN. 1 S.C.F.M.	STATIC PRESSURE IN W.G.	MIN WATTS	REMARKS
EF 1	MEN'S RESTROOM 113	75	0.3	81W	
EF 2	CUSTODIAL CLOSET 112	50	0.3	81W	
EF 3	WOMEN'S RESTROOM 110	75	0.3	81W	

- 1 SET BALANCE DAMPERS SHOWN ON M-1 TO CFM LISTED
- ③ VOLTAGE IS 115/10/60
- ② CONTROL BY ELECTRICAL CONTRACTOR
- 4 PROVIDE MANUAL DAMPER AND BAROMETRIC DAMPER AT EACH EXHAUST FAN OUTLET

	AIR COOLED CONDENSING UNIT SCHEDULE												
MARK	NO. REQ'D	AREA SERVED	MANUFACTURER MODEL NUMBER	MIN.2 SIZE (TONS)	MIN CIRCUIT AMPS	COM NO.	PRES ø	SOR M	OTOR LRA	OFM FLA		REMARKS	4
CU 1	1	WEST ROOMS	123A	4	26.2	1	1	19.9	109.0	1.4			
CU 2	1	EAST ROOMS	123A	4	26.2	1	1	19.9	109.0	1.4			
CU 3	1	CENTRAL ROOMS	123A	3	19.0	1	1	14.1	77.0	1.4			

- 1) REFRIGERANT R-410a
- 2 AT DESIGN CONDITIONS AND 93°F ENTERING AIR TO CONDENSER.
- 3 CONDENSING UNIT MARKS CORRESPOND WITH FURNACE AND COOLING COIL MARK NUMBERS.
- 4 MANUFACTURER FOR MODEL LISTED IS BRYANT, SEE SPECIFICATIONS FOR APPROVED MANUFACTURERS.
- (5) VOLTAGE IS 208/10/60.
- 6 COMBINED FURNACE, COIL AND CONDENSING UNIT WITH CONNECTED REFRIGERANT PIPING MUST MEET THE CAPACITIES LISTED ON COOLING COIL SCHEDULE. SELECT AT 50°F SATURATED SUCTION TEMPERATURE.


	FURNACE SCHEDULE										
MARK	MARK NO. MIN. REQ'D MIN. REQ'D MINIMUM EXT. S.P. MOTOR										
MARK	REQ'D	BTU/HR	BTU/HR	S.C.F.M	IN W.G.	MIN. H.P.	Ø	HERTZ	VOLTS	REMARKS	
F 1	1	80,000	75,000	1600	0.5	1/2	1	60	115	5	
F 2	1	80,000	75,000	1600	0.5	1/2	1	60	115	5	
F 3	1	80,000	75,000	1200	0.5	1/3	1	60	115	5	

- 1 SEA LEVEL RATING
- 2 FURNACE MARKS CORRESPOND WITH CONDENSING UNIT AND COOLING COIL MARKS.
- 3 SEE SPECIFICATIONS FOR APPROVED MANUFACTURERS.
- 4 CAPACITIES SHOWN ARE FOR INDIVIDUAL FURNACES AND NOT FOR TANDEM TOTALS.
- 5 FURNACE TO BE 90% EFFICIENT SEALED COMBUSTION TYPE.

			DX C	OOLIN	IG CC	OIL SO	CHEDU	JLE	1
MARK	NO.	MIN. REC	Q'D CAP.	COND. EN	T. EVAP.	S.C.F.M.	MAX. PR. DR. IN	REMARKS	2
MARK	REQ'D	тот. мвн	SEN. MBH	DB °F	WB °F	3.U.F.M.	W.G.	KEMAKKS	
CC 1	1	35.0	35.0	77.9	58.9	1600	0.25		
CC 2	1	27.5	27.5	78.0	58.9	1600	0.25		
CC 3	1	25.5	25.5	81.0	58.5	1200	0.25		

- 1 COMPLETE WITH FACTORY COIL BOX AND COIL
- 2) SEE SPECIFICATIONS FOR APPROVED MANUFACTURERS.
- 3 COMBINED FURNACE, COIL AND CONDENSING UNIT WITH CONNECTED REFRIGERANT PIPING MUST MEET THE CAPACITIES LISTED ON THIS SCHEDULE. SELECT AT 55°F SATURATED SUCTION TEMPERATURE TEMPERATURE

BAI	OUTSII LANCE	-	
MARK	BALANCE TO CFM	MARK	BALANCE TO CFM
F ₁	110	F 2	100
F 3	340		



EXPIRES 3/31/09

R J Robinson Engineering, P.C.

Mechanical Consulting
P.O. Box 5519, Glendale, AZ 85312-5519
8504 N. 59th AVE., Glendale, AZ.

Phone: (623) 930-1770

Utah Office: 1135 North Main, Bldg. B, Cedar City, UT. 84720
Phone: (435) 867-1702

CHECKED BY: RJR
APPROVED BY: RJR

SHEET NUMBER:

)FFICE


Sheet Title:

R O U

MECHANICAL SCHEDULES

PROJECT NUMBER: DATE: 5 MAY 2008 DRAWN BY: BRR

Revisions:



Sheet Title:


PLUMBING SCHEDULE & SCHEMATICS

Revisions:

15 JULY 2008

PROJECT NUMBER: DATE: 5 MAY 2008 CHECKED BY: RJR APPROVED BY: RJR

SHEET NUMBER:



WATER CALCULATIONS

PRESSURE AVAILABLE AT PRV 50.0 PSI 2.35 PSI LOSS THROUGH PRV PRESSURE AVAILABLE FOR BUILDING SUPPLY 47.65 PSI PIPING LENGTH PRV TO LAST FIXTURE 107 FT MIN. PRESSURE REQUIRED AT FIXTURE 15.0 PSI ALLOWABLE PRESSURE DROP THROUGH PIPING 32.65 PSI

PLUMBING LEGEND

MEANING

CLEANOUT TO GRADE

WALL CLEANOUT

BALL VALVE

FLOOR DRAIN

WITH TRAP PRIMER

SYMBOL OR

ABBREVIATION

VTR

MEANING

HOT WATER LINE

COLD WATER LINE


VENT THRU ROOF

VENT LINE

WASTE LINE

GAS LINE

PIPE FRICTION LOSS ALLOWABLE = <u>ALLOW PRESSURE DROP</u> X 100 FT LENGTH TO MOST DIST FIXTURE $\frac{32.65 \text{ PSI}}{107 \text{ FT}} \times 100 \text{ FT} = 30.0 \text{ PSI PER } 100 \text{ FT}.$



WASTE	& VENT	PIPING S	CHEMATIC	C
SCALE: NONE				P-2

-VERTICAL PRV SEE DETAIL A/P-3 SEE SITE PLAN
FOR CONTINUATION WATER PIPING SCHEMATIC

3/4''

 $\frac{\mathsf{F}}{\mathsf{1}}$

80 CFH

SCALE: NONE

SEE FLOOR PLAN

1/2"

(L-1)

SCALE: NONE

→80 CFH

PROVIDE STUBOUT FOR NATURAL GAS FIRED EMERGENCY GENERATOR

SIZED FOR 678 CFH.

P-2

(WC-1)

GAS METER

SEE SITE PLAN
FOR CONTINUATION

₅3/4"

3

80 CFH

PIPE SIZING BASED UPON IPC

TABLE G102.5(1) FOR NATURAL GAS PIPING. TOTAL CAPACITY OF METER IS 918 CFH, AND LONGEST RUN TO LAST OUTLET IS 55 FT. PLUS 25% FOR FITTINGS IS 69 FT. THE INPUT CAPACITIES LISTED ARE THE MAXIMUM ALLOWED FOR THE EQUIPMENT OR APPLIANCES.

GAS PIPING SCHEMATIC

RÁNDY JAY KÁNDY JAY KOBINSON 15 July 2008_d R J Robinson Engineering, P.C.

SYMBOL OR

ABBREVIATION

WCO

COTG

──|**├**

W/TP


P.O. Box 5519, Glendale, AZ 85312-5519 Phone: (623) 930-1770 8504 N. 59th AVE., Glendale, AZ. Utah Office: 1135 North Main, Bldg. B, Cedar City, UT. 84720 Phone: (435) 867-1702

Sheet Title: PLUMBING DETAILS

Revisions:

PROJECT NUMBER: DATE: 5 MAY 2008 DRAWN BY: BRR CHECKED BY: RJR APPROVED BY: RJR

SHEET NUMBER: Utah Office: 1135 North Main, Bldg. B, Cedar City, UT. 84720 Phone: (435) 867-1702



SCALE: NONE


SCALE: NONE

VERTICAL WATER PRESSURE REDUCING STATION DETAIL SCALE: NONE


1-1/4''-

1-1/4" SUPPLY TO BUILDING


RUN DRAIN TO -FLOOR DRAIN





CLEANOUT TO GRADE DETAIL SCALE: NONE




VENT THRU ROOF (VTR) DETAIL SCALE: NONE








WALL CLEANOUT DETAIL SCALE: NONE



No. 166273 % 6 MAY 2008,5

R J Robinson Engineering, P.C. **Mechanical Consulting** P.O. Box 5519, Glendale, AZ 85312-5519 8504 N. 59th AVE., Glendale, AZ. Phone: (623) 930-1770




MAY 2008


PROJECT NUMBER: J08090 ROYAL ENGINEERING APPROVED BY:

ELECTRICAL MECHANICAL 2335 SOUTH STATE SUITE 225 PROVO, UTAH 84606 PHONE: 801.375.2228 FAX: 801.375.2676

SHEET NUMBER: E1.0

1275 WEST





ELECTRICAL POWER PLAN

SCALE: 1/4" = 1'-0"



PROVIDE AND INSTALL FOR AUTOMATIC DOORS AS REQUIRED. COORDINATE LOCATIONS BEFORE INSTALLATION OF DOOR MULLION.

KEYED NOTES:

VERIFY MOUNTING HEIGHT WITH OWNER/ARCHITECT.


STUB (2) 1" CONDUIT FOR FUTURE ROPES COURSE POWER AND PHONES.

STUB (1) 1" C. WITH (2) #10 CU. AND (1) #10 GND FOR FUTURE SITE LIGHTING.

5 POWER FOR ROOF VENT. TO BE PROVIDED AND INSTALLED BY OTHERS.

STUB (1) 2" CONDUIT FOR FUTURE SOLAR PANELS TO BE LOCATED ON SITE.

2390 WEST HIGHWAY 56 SUITE 4A CEDAR CITY, UTAH 84720 OFFICE: (435) 586-8510 FAX: (435) 586-4873



R O U

G

D E S I G N

H

R G





Sheet Title:

POWER PLAN

Revisions:

PROJECT NUMBER:


J08090 MAY 2008



ELECTRICAL MECHANICAL 2335 SOUTH STATE SUITE 225 PROVO, UTAH 84606 PHONE: 801375.2228 FAX: 801.375.2676

INJUNCTION WITH ROYAL ENGINEERING'S INTERPRETATIONS, CISIONS, DBSERVATIONS AND ADMINISTRATIONS. USE OR PRODUCTION OF THESE DOCUMENTS IN WHOLE OR IN PART WITHOU YAL ENGINEERING'S CONSENT IS IN VIOLATION OF COMMON LAW. PYAL ENGINEERING'S CONSENT IS IN VIOLATION OF COMMON LAW. PYRIGHTS, STATUTORY AND OTHER RESERVED RIGHTS. REFER TO IT 17 U.S.C. PAR. 301 (1991). WHICH PREEMPTS STATE AND LOCAL IBLIC RECORD ACTS. REFER TO ACT 17 U.S.C. PAR. 301 (1991).

SHEET NUMBER: E1.1 Sheet 2 of 6



Sheet Title:

Revisions:

PROJECT NUMBER:

SHEET NUMBER: E2.1 Sheet 3 of 6


APPROVED BY:

DATE:

J08090 MAY 2008

LIGHTING

PLAN




ELECTRICAL LIGHTING PLAN

SCALE: 1/4" = 1'-0"




ELECTRICAL MECHANICAL 2335 SOUTH STATE SUITE 225 PROVO, UTAH 84606 PHONE: 801375.2228 FAX: 801.375.2676 COPYRIGHT® JOB# J08090

THESE DOCUMENTS ARE INSTRUMENTS OF PROFESSIONAL SERVICE AND THE INFORMATION CONTAINED HEREIN IS INCOMPLETE UNLESS IN CONJUNCTION WITH ROYAL ENGINEERING'S INTERPRETATIONS, OBSERVATIONS AND ADMINISTRATIONS. USE OR REPRODUCTION OF THESE DOCUMENTS IN WHOLE OR IN PART WITHOUT ROYAL ENGINEERING'S CONSENT IS IN VIOLATION OF COMMON LAW. COPYRIGHTS, STATUTORY AND OTHER RESERVED RIGHTS. REFER TO ACT 17 U.S.C. PAR. 511 (1991). WHICH PREEMPTS STATE AND LOCAL PUBLIC RECORD ACTS. REFER TO ACT 17 U.S.C. PAR. 301 (1991).



COMMUNICATIONS RISER DIAGRAM



FIXTURE	FIXTURE	FIXTURE	HT FIXTU				TURE	
NUMBER	MANUFACTURER	CATALOG #	TYPE	QTY.	VOLTS	WATTS	MOUNTING	- REMARKS
F1	LITHONIA METALUX DAYBRITE LSI COLUMBIA	2AV G 3 32 MDR GEB 2RDI-332RP-EB81 2AVG332-PMW-1/3-EB 2LLGC 332 SSO RPW STR24-332G-MPO-3EB8LHUNV	F32T8/SP35 ECO	3	120	99	LAY-IN GRID	PROVIDE WITH ELECTRONIC BALLAST
F2	LITHONIA METALUX DAYBRITE LSI COLUMBIA	2AV G 2 32 MDR GEB 2RDI-232RP-EB81 2AVG232-PMW-1/2-EB 2LLGO 232 SSO RPW STR24-232G-MPO-EB8LHUNV	F32T8/SP35	2	120	66	LAY-IN GRID	PROVIDE WITH ELECTRONIC BALLAST
F3								NOT USED
F4	LITHONIA L.A. LIGHTING DAYBRITE METALUX LSI	WS 2 25 A12 GER BAN100-2-3RH-PA-2E8I CD 225W-2/1-EB BE-225-EB81 BR 225 SSO	F25T8/SP35 ECO	2	120	56	SURFACE WALL	PROVIDE WITH ELECTRONIC BALLAST
F5	COLUMBIA LITHONIA METALUX DAYBRITE LIGHTOLIER LSI COLUMBIA	SA3-225-EB8LHUNV LB 2 32 GEB WS-232A-EB81 CAN232-1/2EB WA4A232-S0 PR 232 SSO WCW4-232-EB8LHUNV	F32T8/SP35 ECO	2	120	66	SURFACE CEILING	PROVIDE WITH ELECTRONIC BALLAST
F6	LITHONIA METALUX DAYBRITE LSI COLUMBIA	2GT8 232 A12125 GEB 2GR8-232-EB81 2TG8232-12-1/2EB LA125 232 SD SSO ST824-232G-FSA12.125-EB8LHUNV	F32T8/SP35 ECO	2	120	66	LAY-IN GRID	PROVIDE WITH ELECTRONIC BALLAST
F7	LITHONIA PORTFOLIO OMEGA LIGHTOLIER PRESCOLITE	AH 70M 7AR MD770-7701LI OM870ED17MH-CS DL7A-DL7A/70HC RHD601-70MHFE-STH602	70W MH	1	120	80	RECESSED	
F8	LITHONIA DAYBRITE EXCELINE LUMARK WFHARRIS HUBBELL	TWA 100M LPI WLD100M-LP SPW103MAL MHGP-100H-MT-LL 1200 WP 100MH HPF 120 LP PGM-100H-128-1L	100W MH	1	120	118	SURFACE WALL	
EG1	LITHONIA MCPHILBEN LIGHTGUARD DUAL-LITE	AFN DB EXT PDNBZ UV16LX-HR LSCNI	6W XENON INCLUDED	2	120	12	SURFACE WALL	EMERGENCY EGRESS
ЕМ	BODINE LITHONIA IOTA EELP DUAL-LITE	B50 PS1100 I-80 EB1400 UFO-6W			120			EMERGENCY BALLAST (1)-4 FOOT T8 LAMP, 1100 LUMENS MIN. VERIFY COMPATIBILITY BEFORE ORDERING
EX	LITHONIA MCPHILBEN LIGHTOLIER DUAL-LITE	LQM S W 3 G EL N CXXL-3-GW LDS-N-U-G-W CV-3-G-E-W	INCLUDED	2	120	1.5	UNIVERSAL	NICKEL/CADMIUM BATTERY SINGLE FACE EXIT

CV-3-G-E-W

DUAL-LITE

	EQUIPMENT SCHEDULE										
SYMBOL	DESCRIPTION	SER	VICE	DISCON	NECT	STARTER		LOAD		REMARKS	
STWIDOL	DESCRIPTION	VOLTS	PHASE	SIZE	FUSE	STARTER	HP	VA	AMPS	KLWAKKO	
EF 1	EXHAUST FAN	120 V	1Ø	TOGGLE SWITCH	-	-	-	81	0.7 A	SWITCHED WITH LIGHTING	
WH 1	WATER HEATER	120 V	1Ø	MANUAL STARTER	-	-	ı	1,500	12.5 A		
F 1	FURNACE	120 V	1Ø	MANUAL STARTER	-	-	½ HP	1,176	9.8 A		
F 2	FURNACE	120 V	1Ø	MANUAL STARTER	-	-	½ HP	1,176	9.8 A		
F 3	FURNACE	120 V	1Ø	MANUAL STARTER	-	-	⅓ HP	864	7.2 A		
CU 1	CONDENSING UNIT	240 V	1Ø	60A NEMA 3R	-	-	ı	6,288	26.2 A		
CU 2	CONDENSING UNIT	240 V	1Ø	60A NEMA 3R	-	-	-	6,288	26.2 A		
CU 3	CONDENSING UNIT	240 V	1Ø	30A NEMA 3R	-	-	ı	4,560	19.0 A		
NOTES:				INCIVIA 3R							


SCALE: NONE

SCALE: NONE

- . VERIFY ALL EQUIPMENT LOCATIONS AND CONNECTION REQUIREMENTS (i.e. VOLTAGE, PHASE, FLA, ETC.) WITH
- MECHANICAL DRAWINGS/SUBMITTALS BEFORE BEGINNING ROUGH IN. . ALL FUSES SHALL BE DUAL ELEMENT TIME DELAY. FINAL BREAKER/FUSE & DISCONNECT SIZE SHALL BE DETERMINED
- BY MANUFACTURER'S RECOMMENDATION FOR ACTUAL EQUIPMENT INSTALLED.
- . MAXIMUM VALUES INDICATED.

								PANEL	SCHI	EDULE	"LA'	•							
/OLT	AGE:	240	/ 120 VOLTS				BUS RA	TING (AN	MPS):	225			R	EMAR	KS:	* SEE ONE-LINE DIAGRAM FOR RATING.			
MOUN	TING:	SURF	ACE	PH	ASE:	1	MAIN L	UGS ONL	Υ										
NCLO	SURE:	NEMA	A 1	WIF	RE:	3	SHORT	CIRCUIT	RATING:	22,000	AMPS (R	MS-SYN	1)						
BF	REAKE	R		_	FEEDE	ER .			LOAD/PH		CKT. L	.OAD	FE	EDER			В	REAKE	ĒR
No.	AMPS	POLE	CIRCUIT NAME	С	WIRE	GRD	DEMAND FACTOR	WATTS	ØA	ØВ	WATTS	DEMAND FACTOR	GRD	WIRE	С	CIRCUIT NAME	POLE	AMPS	No.
1	20	1	REC-CAD/CAM RM 115	3/4"	#12	#12	1.00	900	2,154	ż	1,254	1.00	#12	#12	3/4"	WEST OFFICE AREA LTG	1	20	2
3	20	1	REC-CAD/CAM RM 115	3/4"	#12	#12	1.00	720		1,974	1,254	1.00	#12	#12	3/4"	EAST OFFICE AREA LTG	1	20	4
5	20	1	REC-CAD/CAM 115 COPIER	3/4"	#12	#12	1.00	180	1,298	3	1,118	1.00	#12	#12	3/4"	CORRIDOR AREA LTG	1	20	6
7	20	1	REC-CAD/CAM 115 PLOTTER	3/4"	#12	#12	1.00	180		1,398	1,218	1.00	#12	#12	3/4"	SOUTH/CONFERENC AREA LTG	1	20	8
9	20	1	REC-CAD/CAM 115/HALL 117	3/4"	#12	#12	1.00	900	1,640	-	740	1.00	#12	#12	3/4"	EXTERIOR LTG	1	20	10
11	20	1	REC-MANAGER 119	3/4"	#12	#12	1.00	900		2,076	1,176	1.00	#12	#12	3/4"	F-2	1	20	12
13	20	1	REC-BUSINESS 120	3/4"	#12	#12	1.00	900	1,764		864	1.00	#12	#12	3/4"	F-3	1	20	14
15	20	1	REC-ENTRY 100/RECEPT. 122	3/4"	#12	#12	1.00	900		2,076	1,176	1.00	#12	#12	3/4"	F-1	1	20	16
17	20	1	REC-CINDY'S OFFICE 102	3/4"	#12	#12	1.00	720	3,864		3,144	1.00	#10	#8	3/4"	CU-1	2	40	18
19	20	1	REC-DAVID'S OFFICE 103	3/4"	#12	#12	1.00	900		4,044	3,144	1.00	-	#8	-	-	-	-	20
21	20	1	REC-MANAGER 104	3/4"	#12	#12	1.00	720	3,000		2,280	1.00	#10	#10	3/4"	CU-3	2	30	22
23	20	1	REC-MANAGER 105	3/4"	#12	#12	1.00	720		3,000	2,280	1.00	-	#10	-	-	-	-	24
25	20	1	REC-MANAGER 107	3/4"	#12	#12	1.00	900	4,044		3,144	1.00	#10	#8	3/4"	CU-2	2	40	26
27	20	1	REC-MANAGER 108/STORAGE 109	3/4"	#12	#12	1.00	900		4,044	3,144	1.00	-	#8	-	-	-	-	28
29	20	1	REC-RESTROOM/HALL	3/4"	#12	#12	1.00	900	2,400		1,500	1.00	#12	#12	3/4"	WH-1	1	20	30
31	20	1	EWC	3/4"	#12	#12	1.00	500		680	180	1.00	#12	#12	3/4"	FACP	1	20	32
33	20	1	TEL. TERM BOARD	3/4"	#12	#12	1.00	360	1,560		1,200	1.00	#12	#12	3/4"	AUTOMATIC DOOR	1	20	34
35	20	1	REC-CONFERENCE ROOM 116	3/4"	#12	#12	1.00	1,080	}	2,280	1,200	1.00	#12	#12	3/4"	IRRIGATION CONTROLLER	1	20	36
37	20	1	REC-WORKROOM 121	3/4"	#12	#12	1.00	720	1,920		1,200	1.00	#12	#12	3/4"	ROOF VENT	1	20	38
39	20	1	REC-FRIDGE	3/4"	#12	#12	1.00	1,000		2,000	1,000	1.00	#12	#12	3/4"	REC - COPIER	1	20	40
41			SPACE				1.00		0							SPACE			42

CONNECTED LOAD (VA) CONNECTED LOAD (A) DEMAND FACTOR ADJUSTMENTS (VA) TOTAL LOAD (VA) TOTAL LOAD (A) PHASE LOADING (%)




ALL INSULATION ON CONDUCTORS TO BE THHN UNLESS NOTED OTHERWISE. INSULATION ON ALL UNDERGROUND EXTERIOR CONDUCTORS SHALL BE THHW. INSULATION ON ALL UNDERGROUND EXTERIOR CONDUCTORS SHALL

- 2. LOAD DEMANDS CALCULATED AS PER SECTIONS 210 & 220 OF THE NATIONAL
- 3. PANEL COVER SHALL BE FIELD MARKED FOR FLASH PROTECTION WITH A PERMANENT LABEL AS REQUIRED BY THE NATIONAL ELECTRICAL CODE SECTION 110. LABEL SHALL READ AS FOLLOWS: "DANGER: POTENTIAL ARC FLASH HAZARD"
- 4. ABBREVIATIONS: REC-CONVENIENCE OUTLET, RR-RESTROOM, (N)ORTH, (S)OUTH, (E)AST (W)EST

KEYED NOTES:

CONTRACTOR TO INSTALL JACKS, CAT6 CABLE AND PATCH PANEL. SUU PERSONNEL TO TERMINATE CABLES AT PATCH PANEL.

SIMPLEX EQUIPMENT TO BE PROVIDED BY SUU PERSONNEL. EQUIPMENT TO BE INSTALLED AND PROGRAMMED BY CONTRACTOR.



G R O U P

D E S I G N

⊢ Z





Sheet Title:

RISERS & SCHEDULES

Revisions:

PROJECT NUMBER:

DRAWN BY:

CHECKED BY:

J08090

MAY 2008


ROYAL ENGINEERING
ELECTRICAL MECHANICAL


2335 SOUTH STATE SUITE 225 PROVO, UTAH 84606 PHONE: 801.375.2228 FAX: 801.375.2676


COPYRIGHT®

THESE DOCUMENTS ARE INSTRUMENTS OF PROFESSIONAL SERVICE AND THE INFORMATION CONTAINED HEREIN IS INCOMPLETE UNLESS IN CONJUNCTION WITH ROYAL ENGINEERING'S INTERPRETATIONS, DECISIONS, OBSERVATIONS AND ADMINISTRATIONS. USE OR REPRODUCTION OF THESE DOCUMENTS IN WHOLE OR IN PART WITHOUT ROYAL ENGINEERING'S CONSENT IS IN VIOLATION OF COMMON LAW. COPYRIGHTS, STATUTORY AND OTHER RESERVED RIGHTS, REFER TO ACT 17 U.S.C. PAR. 511 (1991). WHICH PREEMPTS STATE AND LOCAL PUBLIC RECORD ACTS. REFER TO ACT 17 U.S.C. PAR. 301 (1991). SHEET NUMBER: E3.1


SCALE. N	ONE		
	ELECTRICA	L SYN	/IBOLS
NOTE: A	ALL SYMBOLS MAY NOT BE USED EXPLANATION	DOT [*] SYMBOL	TED SYMBOLS INDICATE EXISTING FIXTURE, EQUIPMENT, ETC. EXPLANATION
	BRANCH CIRCUIT CONCEALED IN CEILING OR WALL	\$	SINGLE POLE SWITCH (SUBSCRIPT AS INDICATED BELOW)
	BRANCH CIRCUIT CONCEALED IN GROUND OR FLOOR	2	TWO POLE SWITCH
		3 4	3-WAY SWITCH 4-WAY SWITCH
A-1,3	BRANCH CIRCUIT HOMERUNS TO PANEL	D	DIMMER SWITCH
	LIGHTING AND POWER PANELBOARD	K T	KEYED SWITCH TIMER SWITCH
CH 1	MECHANICAL EQUIPMENT SYMBOL	M F OC	MANUAL STARTER WITH THERMAL OVERLOAD EXHAUST FAN TIMER SWITCH
1	KEYED NOTE REFERENCE	00	OCCUPANCY SENSOR SWITCH
0	JUNCTION BOX	\$°\$°	CONTROLLING SWITCH (LETTER INDICATES CONTROL CIRCUIT)
=	DUPLEX RECEPTACLE OUTLET	ŚŚ	DOUBLE GANG SWITCH
	WP ——MODIFIER = A-3 ——PANEL SPACE ASSIGNMENT REF ——EQUIPMENT DESIGNATION	(\$)	OCCUPANCY SENSOR SWITCH (CELLING MOUNTED)
	WP WEATHERPROOF COVER GFCI PROTECTED BY FAULT CIRCUIT INTERRUPTER +44 MOUNTING HEIGHT ABOVE FLOOR OR GRADE GIVEN IN INCHES.	9	MOTOR OUTLET
	REF REFRIGERATOR	Ф	THERMOSTAT OUTLET
	DW DISHWASHER DISP DISPOSAL	S	REMOTE SENSOR OUTLET
	WASH WASHING MACHINE EWC ELECTRIC WATER COOLER		EXHAUST FAN
⊕	QUAD RECEPTACLE OUTLET	-®	BELL
←	SPLIT WIRED DUPLEX RECEPTACLE OUTLET	•	PUSHBUTTON
WP GFCI ⊕	DUPLEX RECEPTACLE WEATHERPROOF AND GFCI	(V)	VOLUME CONTROL
_{GFCI} ⊕	DUPLEX RECEPTACLE OUTLET WITH GROUND FAULT CIRCUIT INTERRUPTION PROTECTION		SPEAKER
EWC ←	RECEPTACLE ELECTRIC WATER COOLER (EWC)	¥	TELEPHONE OUTLET
€	220V RECEPTACLE OUTLET	\triangleright	COMPUTER DATA OUTLET
⊕ =	ISOLATED GROUND RECEPTACLE	T	NETWORK AND VOICE OUTLET
Ф	RECEPTACLE FLOOR MOUNTED	TV	TELEVISION OUTLET
	RECEPTACLE CEILING MOUNTED	®	PHOTOCELL
(a)	SPECIAL RECEPTACLE	E	FIRE ALARM PULL STATION
Ď	DISCONNECT SWITCH	×	FIRE ALARM HORN/STROBE
⊠₁	MOTOR STARTER	Ø	FIRE ALARM STROBE
<u> </u>	FLUORESCENT FIXTURE (TYPICAL)	0	SMOKE DETECTOR (SUBSCIPT AS INDICATED BELOW)
EW	EMERGENCY LIGHTING UNIT	A B	SMOKE ALARM SMOKE ALARM BATTERY-BACKED
¢	SURFACE OR PENDANT MOUNTED FIXTURE	D R	DUCT SMOKE DETECTOR SMOKE DETECTOR WITH ELEVATOR RECALL MODULE
	RECESSED FIXTURE	1	HEAT DETECTOR
þ	WALL MOUNTED FIXTURE	⊦⊗	WALL MOUNTED EXIT LIGHT (SINGLE FACE)
6	WALL PACK	⊦ ₫	WALL MOUNTED EXIT LIGHT (DOUBLE FACE)
	FLUORESCENT STRIP	8	CEILING MOUNTED EXIT LIGHT
	TRACK LIGHTING	₫	CEILING MOUNTED EXIT LIGHT (DOUBLE FACE)
	EMERGENCY LIGHTING UNIT		TAMPER AND FLOW VALVES
F1	FIXTURE TYPE SYMBOL	(F)	
135	ROOM NUMBER	F/S	FIRE/SMOKE DAMPER
©	CONDUIT STUB		SECURITY CAMERA







SCALE: NONE



DRAWN BY: CHECKED BY: **MECHANICAL** APPROVED BY: FAX: 801.375.2676 JOB# J08090 HESE DOCUMENTS ARE INSTRUMENTS OF PROFESSIONAL SERVICE NO THE INFORMATION CONTAINED HEREIN IS INCOMPLETE UNLESS IN ONJUNCTION WITH ROYAL ENGINEERING'S INTERPRETATIONS, JECISIONS, OBSERVATIONS AND ADMINISTRATIONS. USE OR EPRODUCTION OF THESE DOCUMENTS IN WHOLE OR IN PART WITHOUT GOVAL ENGINEERING'S CONSENT IS IN VIOLATION OF COMMON LAW. COPYRIGHTS, STATUTORY AND OTHER RESERVED RIGHTS. REFER TO ACT 17 U.S.C. PAR. 511 (1991).


SHEET NUMBER: E3.2 Sheet


CEDAR (OFFIC FAX: H ~

Ь

G R O U

DESIGN ARCHITECTURE






|Sheet Title:

ELECTRICAL **DETAILS**


Revisions:


PROJECT NUMBER:


J08090 MAY 2008




SCALE: NONE











ELECTRICAL DEVICE MOUNTING HEIGHTS INSTALLATION DETAIL SCALE: NONE







G R O U

D E S I G N

H

ELECTRICAL **DETAILS**

Revisions:

		PROJECT NUMBER: DATE: DRAWN BY:	J08090 MAY 2008 AMI
ROYAL ENG		CHECKED BY:	SRO
ELECTRICAL 2335 SOUTH STATE SUITE PHONE: 801.375.2228	MECHANICAL 225 PROVO, UTAH 84606 FAX: 801.375.2676	APPROVED BY:	SRO
COPYRIGHT®	JOB# J08090		
THESE DOCUMENTS ARE INSTRUMENTS AND THE INFORMATION CONTAINED CONJUNCTION WITH ROYAL ENGINE DECISIONS, OBSERVATIONS AND ACREPRODUCTION OF THESE DOCUME ROYAL ENGINEERING'S CONSENT IS COPYRIGHTS, STATUTORY AND OTHE ACT 17 U.S.C. PAR. 511 (1991). WHE PUBLIC RECORD ACTS. REFER TO ACT	HEREIN IS INCOMPLETE UNLESS IN ERING'S INTERPRETATIONS, OMINISTRATIONS, USE OR NTS IN WHOLE OR IN PART WITHOUT IN VIOLATION OF COMMON LAW, OR RESERVED RIGHTS, REFER TO HIGH PREEMPTS STATE AND LOCAL	SHEET NUMBER: Sheet 6 of	E3.3